

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 66412				

SCHEDULE OF QUANTITIES

LIGHTING SCHEDULE

LOCATION	LOCATING UNDERGROUND CABLE FOOT 80300100	ELECTRIC SERVICE INSTALLATION EACH 80400100	GROUNDING ELECTRODE BELOW GRADE EACH 80600200	CONDUIT PUSHED 2" DIA. INT. METAL FOOT 81020500	CONDUIT PUSHED 4" DIA. INT. METAL FOOT 81020900	TRENCH AND BACKFILL ELECTRICAL WORK FOOT 81500200	UNIT DUCT 2 #8 XLP 1#8 XLPG 3/4" P FOOT 81600215	LUMINAIRE SODIUM VAP. HORIZ MOUNT 250 WATT EACH 82102250	LUMINAIRE SODIUM VAP. HIGH MAST MULTI MOUNT 400 WATT EACH 82105400	LIGHTING CONTROLLER CB-RCS 60A 480 VOLT EACH 82500520	LIGHT POLE STEEL 45' M.H. TENON MOUNT-TWIN EACH 83035400	LIGHT TOWER 100 FT MH LUMINAIRE MT. 4 EACH 83502300	LIGHT TOWER FOUNDATION 48" DIA. FOOT 83700100	LIGHT POLE FOUNDATION METAL 15" BC, 8" X 8" EACH 83600357	BREAKAWAY DEVICE COUPLING SS SCREEN EACH 83800650	
F.A.I. 80																
805+41.00, 105' LT									4			1	14			
820+60.23, 67.5' LT TO 67.5' RT				135												
834+23.00, 113' LT									4			1	14			
F.A.P. 623 (SENECA ROAD)																
13+44.00, 60.0' RT								2			1			1	4	
13+52.00, 42.5' LT TO 42.5' RT					85											
14+59.31, 116.08' LT										1						
14+68.00, 53.0' LT								2			1			1	4	
23+47.00, 32.5' LT TO 32.5' RT					65											
23+71.00, 53.0' RT								2			1			1	4	
24+95.00, 65.3' LT								2			1			1	4	
RAMP B																
151+35.00, 32.5' LT TO 32.5' RT				65												
RAMP C																
220+76.00, 32.5' LT TO 32.5' RT				65	65											
TOTALS	150	1	1	265	215	4650	5115	8	8	1	4	2	28	4	16	

LIGHTING REMOVAL SCHEDULE

LOCATION	REMOVAL EX. LIGHTING UNIT SALVAGE EACH 84200500	LIGHTING FOUNDATION REMOVAL, PARTIAL EACH 84200705	REMOVAL LIGHTING CONTROLLER EACH 84500110	REMOVAL ELECTRIC INSTALLATION EACH 84500120	REMOVAL LIGHTING CONTROLLER FOUNDATION EACH 81400130	REMOVE EXISTING HIGH MAST LIGHT TOWER EACH X8420220
F.A.P. 623 (SENECA ROAD)						
10+80.82, 63.14' LT				1		
10+93.52, 63.39' LT			1		1	
15+05.11, 55.96' LT						
15+22.08, 41.12' LT	4	1				1
23+62.83, 40.63' LT	4	1				1
RAMP C						
209+74.77, 23.84' RT	4	1				1
RAMP D						
260+88.30, 28.90' RT	4	1				1
TOTALS	16	4	1	1	1	4

ENTIRE SHEET REVISED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**I-80 (F.A.I. 80) AT
 SENECA ROAD (F.A.P. 623)
 GRUNDY COUNTY**
 SCHEDULE OF QUANTITIES

SCALE: N.T.S.
 DATE 10/14/05

DRAWN BY NMR/BJG
 CHECKED BY DJL/JPL

REVISED 1-6-06 MJ