

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 66412				

NO.	PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	IM	IM	BRI	IM	
					90% FED 10% STATE GRUNDY CO.	90% FED 10% STATE	80% FED 20% STATE GRUNDY CO.	90% FED 10% STATE GRUNDY CO.	SAFETY SFTY-3N
					ROADWAY J000-2A	LASALLE 1000	SN 032-0114 BRIDGE X771-2A	LIGHTING Y030-IE	
93	60221700	MANHOLE TYPE A, 5' DIA. TYPE 8 GRATE	EACH	1	0	1			
94	60235800	INLETS, TYPE A, TYPE 4 FRAME AND GRATE	EACH	2	2				
95	60622400	CONCRETE MEDIAN, TYPE SM-6.06	SO FT	400	400				
96	60624600	CORRUGATED MEDIAN	SO FT	1620	1620				
97	60625800	ISLAND PAVEMENT (SPECIAL)	SO YD	14575	14575				
98	60900315	TYPE D INLET BOX, STANDARD 609006	EACH	4	4				
99	61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	1250	1250				
100	61100605	MISCELLANEOUS CONCRETE	CU YD	7	7				
101	61101009	STORM SEWERS PROTECTED, CLASS A 8"	FOOT	100	100				
102	61101011	STORM SEWERS PROTECTED, CLASS A 10"	FOOT	100	100				
103	61101013	STORM SEWERS PROTECTED, CLASS A 12"	FOOT	528	528				
104	61101016	STORM SEWERS PROTECTED, CLASS A 14"	FOOT	100	100				
105	61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	15	15				
106	61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	20	20				
107	61139900	STORM SEWERS, SPECIAL 6"	FOOT	1050	1050				
108	61140000	STORM SEWERS, SPECIAL 8"	FOOT	391	391				
109	61140100	STORM SEWERS, SPECIAL 10"	FOOT	100	100				
110	61140200	STORM SEWERS, SPECIAL 12"	FOOT	579	579				
111	61140300	STORM SEWERS, SPECIAL 14"	FOOT	100	100				
* 112	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2712.5	2600	112.5			
* 113	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	0	1			
* 114	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2				
* 115	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2				
* 116	63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	12	12				
117	63200310	GUARDRAIL REMOVAL	FOOT	5095	4475	620			
118	63300740	TEMPORARY GUARD RAIL	FOOT	1340	1340				
119	63300775	TEMPORARY TERMINAL SECTION	EACH	4	4				
120	63400105	GUARD POSTS	EACH	40	40				
121	63400205	GUARD POSTS REMOVAL	EACH	40	40				
122	63500105	DELINEATORS	EACH	234	154	80			
123	64200105	SHOULDER RUMBLE STRIPS	FOOT	19802	19802				
124	66500105	WOVEN WIRE FENCE, 4'	FOOT	12179	11337	842			
125	66502000	WOVEN WIRE FENCE GATES, 4'x24' DOUBLE	EACH	2	0	2			
126	66502300	WOVEN WIRE FENCE REMOVAL	FOOT	10725	10145	580			
127	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	48	48				
128	66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3				
129	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10				
130	67100100	MOBILIZATION	L SUM	1	1				
131									
132	X7011420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	L SUM	1	1				
133	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
134	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
135									
136	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1				
137									
138	70103800	TRAFFIC CONTROL (SPECIAL)	L SUM	1	1				

* SPECIALTY ITEMS

11/15/2005 V:\CHICAGO\DOT\1886\CAD\dwg\1836_SUM_QNTY_03.dgn



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**I-80 (F.A.I. 80) AT
 SENECA ROAD (F.A.P. 623)
 GRUNDY COUNTY**
 SUMMARY OF QUANTITIES
 SCALE: VERT. DRAWN BY NMR/TCH
 HORIZ. CHECKED BY DJL/CML
 DATE 10/14/05