

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 66412				

NO.	PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	IM	IM	BRI	IM	
					90% FED 10% STATE GRUNDY CO.	90% FED 10% STATE	80% FED 20% STATE GRUNDY CO.	90% FED 10% STATE GRUNDY CO.	10% STATE
					ROADWAY J000-2A	LASALLE 1000	SN 032-0114 BRIDGE X771-2A	LIGHTING Y030-IE	SAFETY SFTY-3N
* 185	83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	30				30	
* 186	83700350	LIGHT TOWER FOUNDATION, 54" DIAMETER	FOOT	36				36	
* 187	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	16				16	
* 188	84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	4				4	
* 189	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1				1	
* 190	84500120	REMOVAL OF ELECTRIC INSTALLATION SERVICE	EACH	1				1	
* 191	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1				1	
192	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	4	4				
193	X3550300	BITUMINOUS BASE COURSE, SUPERPAVE 6"	TON	850	850				
194	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C" N50	TON	415	19	396			
195	X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E" N90	TON	2429	2429				
196	X4066765	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N50	TON	707	707				
197	X4066770	LEVELING BINDER (MACHINE METHOD) SUPERPAVE N70	TON	497	497				
198	X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	19542	19542				
199	X6013820	PIPE UNDERDRAIN OUTLET EXTENSION SPECIAL	EACH	9	9				
200	X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	39	39				
201	X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	2479	2479				
202	X6065701	CONCRETE MEDIAN, TYPE SM-4.06	SQ FT	2443	2443				
203	X8420220	REMOVE EXISTING HIGH MAST LIGHT TOWER	EACH	4				4	
204	XX005347	BITUMINOUS CONCRETE BINDER COURSE, IL 19.0 N50	TON	6,659	6,214	445			
205	XX005430	MAINTENANCE OF EXISTING HIGHWAY LIGHTING	L SUM	1				1	
* 206	XX005466	FURNISHING AND INSTALLING GUARDRAIL END SHOES	EACH	1	0	1			
207	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	48058	48058				
208	Z0002600	BAR SPLICERS	EACH	124			124		
* 209	Z0008230	DRILLED SHAFT IN SOIL 30"	FOOT	600			600		
210	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
211	Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2					2
212	Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2					2
213	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	9					9
214	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), NARROW, TEST LEVEL 3	EACH	3					3
215	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1					1
216	Z0047300	PROTECTIVE SHIELD	SQ YD	420			420		
217	Z0076600	TRAINEES	HOUR	2,000	2,000				
218	Z0001058	AGGREGATE SUBGRADE 18"	SQ YD	1528	1528				
219									
220	Z8500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	300	300				
221	48300410	PCC SHOULDERS 9 1/2"	SQ YD	16,285	16,285				
222	50104650	SLOPE WALL REMOVAL	SQ YD	300	300				
223	63500120	DELINEATOR REMOVAL	EACH	154	154				
224	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	500	500				
225	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	348	348				

* SPECIALTY ITEMS

0 Y080

Louis Berger & Associates, Inc.
100 Elm Street, Suite 300
Manchester, NH 03101
(603) 644-5200

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**I-80 (F.A.I. 80) AT
SENECA ROAD (F.A.P. 623)
GRUNDY COUNTY**
SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY NMR/TCH
 HORIZ. CHECKED BY DJL/CML
DATE 10/14/05

11/15/2005 V:\CHICAGO\DOT\1836\CAD\dwg\1836_SUM_QNTY_05.dwg