

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HR	GRUNDY	171	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 66412				

# SCHEDULE OF QUANTITIES

EARTHWORK QUANTITIES										
LOCATION	CUT (CU. YD.)	FILL (CU. YD.)	TOPSOIL EXCAVATION (CU. YD.)	UNSUITABLE MATERIAL (CU. YD.)	EARTH EXCAVATION (CU. YD.) 20200100	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU. YD.)	FURNISHED EXCAVATION (CU. YD.) 20400800	TOPSOIL EXCAVATION AND PLACEMENT (CU. YD.) 21101505	EXCESS TOPSOIL (CU. YD.)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU. YD.) 20201200
F.A.P. 623 (SENECA ROAD)	7990	77165	5960		7990	5993	71173	4165	1795	
RAMP A	4295	5270	1595		4295	3221	2049	1255	340	
RAMP B	9875	6160	2345		9875	7406	-1246	1770	575	
RAMP C	22810	19035	3725		22810	17108	1928	2710	1015	890
RAMP D	19605	18760	2780		19605	14704	4056	2125	655	
FRONTAGE ROAD	5210	2125	2455		5210	3908	-1783	1352	1103	
DRIVEWAY	145	395	95		145	109	286	70	25	
TEMPORARY RAMP B	6060	6020			6060	4545	1475			
TEMP. WIDEN SENECA RD	445	450			445	334	116			
LOCKED GATE EBACC	610	2380	820		610	458	1923	520	300	
LOCKED GATE WBACC	970	290	560		970	728	-438	260	300	
TOTAL	78015	138050	20335		78015	58512	79539	14227	6108	890

SEEDING								
LOCATION	CLASS 2A (ACRE) 25000210	CLASS 4A (ACRE) 25000312	TEMP. EROSION CONTROL SEEDING (POUND) 28000250	NITROGEN FERTILIZER NUTRIENT (POUND) 25000400	PHOSPHOROUS FERTILIZER NUTRIENT (POUND) 25000500	POTASSIUM FERTILIZER NUTRIENT (POUND) 25000600	MULCH METHOD 2 (TON) 25100120	EROSION CONTROL BLANKET (SQ YD) 25100630
F.A.P. 623 (SENECA ROAD)	9.30	2.10	2280	837	837	837	23.0	5270
RAMP A	2.50	0.40	580	225	225	225	6.0	540
RAMP B	2.60	1.40	800	234	234	234	8.0	1120
RAMP C	3.00	3.80	1360	270	270	270	14.0	940
RAMP D	2.90	1.60	900	261	261	261	9.0	1670
FRONTAGE ROAD	1.20	1.60	560	108	108	108	6.0	1830
LOCKED GATE EBACC	0.10	0.10	40	9	9	9	1.0	1100
LOCKED GATE WBACC	0.10	0.10	40	9	9	9	1.0	270
TOTAL	21.7	11.10	6480	1953	1953	1953	68.0	12740

REVISIONS	
NAME	DATE
MJ	12-6-05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**I-80 (F.A.I. 80) AT  
SENECA ROAD (F.A.P. 623)  
GRUNDY COUNTY**  
SCHEDULE OF QUANTITIES  
SCALE: N.T.S. DRAWN BY NMR/BJG  
DATE 10/14/05 CHECKED BY DJL/JPL