

# SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 66412				

## PAVEMENT QUANTITIES

LOCATION	AGGREGATE SUBGRADE 12"	AGGREGATE SUBGRADE 18"	PORTLAND CEMENT CONCRETE PAVEMENT 9/2" (JOINTED)	STABILIZED SUB-BASE 4"	AGGREGATE SHOULDERS TYPE B	AGGREGATE SURFACE COURSE, TYPE A - 10"	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	AGGREGATE BASE COURSE TYPE A-8"	BITUMINOUS BASE COURSE SUPERPAVE 6"	INCIDENTAL BITUMINOUS SURFACING	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX "C" N50	POLYMERIZED BIT. CONC. SURFACE COURSE SUPERPAVE MIX "E" N90	BITUMINOUS SHOULDERS 10"	AGGREGATE SURFACE COURSE TYPE B	LEVELING BINDER (MACH. METH.) SUPERPAVE N70	LEVELING BINDER (MACH. METH.) SUPERPAVE N50	AGGREGATE BASE COURSE TYPE B 6"	BIT. CONC. BINDER COURSE SUPERPAVE N50	PORTLAND CEMENT CONCRETE SHOULDERS 9/2"
	(SQ. YD.) Z0001050	(SQ. YD.) Z3001686	(SQ. YD.) 42000411	(SQ. YD.) 31200100	(TON) 48101200	(SQ YD)	(SQ YD) 21001000	(SQ YD) 35100700	(SQ YD) X3550300	(TON) 40800040	(TON) X4066414	(TON) X4066538	(SQ. YD.) 48200800	(CU YD) 40200800	(TON) X4066770	(TON) X4066765	(SQ YD) 35101800	(TON) X4066765	(SQ. YD.) 48300410
F.A.I. 80																			
791+36.34 LT TO 840+80.62 LT												1250							
800+52.69 RT TO 846+32.92 RT												1179							
807+23.71 LT TO 811+60.00 LT					44								485						
808+15.65 RT TO 811+10.00 RT					30								328						
830+00.00 LT TO 833+17.57 LT					53								576						
827+80.00 RT TO 830+52.33 RT					28								303						
F.A.P. 623 (SENECA ROAD)																			
0+25.00 TO 36+11.55	20052		12702	14955	0		23519				19								5567
32+38.93 LT														46					
33+12.64 LT														46					
6+41 LT								311	300	30									
RAMP A																			
98+96.88 TO 119+09.21	5952		3221	4343	420		5952												2774
RAMP B																			
150+00.00 TO 177+82.37	7895		5097	5892	490		7895	300	30										2536
RAMP C																			
198+96.89 TO 221+54.06	5846		4313	4838	508		5846												2520
* 210+00.00 TO 214+50.00		1528																	
RAMP D																			
250+00.00 TO 279+25.94	8313		5438	6226	547		8313												2888
FRONTAGE ROAD																			
300+00.00 TO 334+00.00					775	6855	6800												
326+00 LT														36					
DRIVEWAY																			
401+15.00 TO 403+09.18					29			676	550	60									
TEMPORARY RAMP B																			
151+00 TO 157+90															497		1004		
TEMP. WIDENING SENECA RD																			
25+80.00 TO 38+40.00																707	1427		
LOCKED GATE EBACC																			
10+00.00 TO 19+16.22					150			1990			193								217
LOCKED GATE WBACC																			
50+00.00 TO 159+31.84					155			2076			203								228
TOTAL	48058	1528	30771	36254	3307	6855	58325	5053	850	90	415	2429	1692	128	497	707	2431	445	16285

\* SUBGRADE UNDERCUT AREA

REVISIONS	
NAME	DATE
MJ	12.6.05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**I-80 (F.A.I. 80) AT  
 SENECA ROAD (F.A.P. 623)  
 GRUNDY COUNTY**  
 SCHEDULE OF QUANTITIES

SCALE: N.T.S.  
 DATE 10/14/05

DRAWN BY NMR/BJG  
 CHECKED BY DJL/JPL