

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO.		66412		

SCHEDULE OF QUANTITIES

PIPE UNDERDRAIN SCHEDULE	
LOCATION	4" (MODIFIED) (FOOT) X6013600
F.A.P. 623 (SENECA ROAD)	
LT 3+41 - 18+18	1472
RT 3+00 - 18+18	1472
LT 20+82 - 35+00	1418
RT 20+82 - 35+00	1418
RAMP A	
RT 99+00 - 101+35	235
RT 101+55 - 109+93	838
LT 101+95 - 109+93	798
RT 109+93 - 114+50	457
LT 109+93 - 114+50	457
RAMP B	
RT 154+50 - 159+50	500
LT 154+50 - 159+50	500
RT 159+50 - 166+25	675
LT 159+50 - 166+25	675
RT 166+25 - 175+38	913
RT 175+58 - 177+86	228
LT 166+25 - 169+36	311
RAMP C	
RT 199+00 - 206+50	750
LT 201+95 - 206+50	455
RT 206+50 - 211+52	502
LT 206+50 - 211+52	502
RT 211+52 - 216+50	498
LT 211+52 - 216+50	498
RAMP D	
LT 255+00 - 262+33	733
RT 255+00 - 262+33	733
LT 262+33 - 267+52	519
RT 262+33 - 267+52	519
LT 267+72 - 270+80	308
RT 267+72 - 279+30	1158
TOTALS	19542

PIPE UNDERDRAIN SPECIAL SCHEDULE		
LOCATION	4" (FOOT) 60108100	CONC. HEADWALLS (EACH) 60100060
F.A.P. 623 (SENECA ROAD)		
LT 3+41	19	1
RT 3+00	19	1
RT & LT 8+18	20	2
RT & LT 13+18	20	2
LT 25+00	20	1
RT 25+00	18	1
RT & LT 30+00	19	2
RT & LT 35+00	19	2
RAMP A		
RT 101+35	19	1
RT 106+00	35	1
RT 106+00	19	1
RT 109+93	36	1
RT 109+93	78	1
RAMP B		
RT 159+50	38	1
RT 159+50	74	1
RT 162+75	56	1
RT 169+36	37	1
RT 171+00	19	1
RT 175+38	19	1
RT 177+86	19	1
RAMP C		
RT 199+00	13	1
RT 201+95	35	1
RT 202+75	13	1
LT & RT 210+00	31	2
RT 211+52	48	1
LT 211+52	72	1
RAMP D		
LT & RT 259+00	39	2
RT 262+33	106	2
RT 265+00	54	1
RT 267+72	20	1
RT 270+00	20	1
RT 275+00	20	1
TOTALS	1074	39

LOCATION	PIPE UNDERDRAIN OUTLET EXTENSION SPECIAL (EACH) X6013820	SHOULDER REMOVAL AND REPLACEMENT (FOOT) 60100070
F.A.I. 80		
802+89 LT	1	33
803+19 LT	1	33
802+85 RT	1	25
803+22 RT	1	25
832+63 RT	1	36
833+60 LT	1	28
837+63 LT	1	18
839+00 RT	1	21
842+04 RT	1	17
TOTALS	9	236

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**I-80 (F.A.I. 80) AT
 SENECA ROAD (F.A.P. 623)
 GRUNDY COUNTY**
 SCHEDULE OF QUANTITIES

SCALE: N.T.S.
 DATE 10/14/05

DRAWN BY NMR/BJG
 CHECKED BY DJL/JPL