

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	32-2HBR	GRUNDY	171	28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 66412				

SCHEDULE OF QUANTITIES

LIGHTING SCHEDULE

LOCATION	LOCATING UNDERGROUND CABLE FOOT 80300100	ELECTRIC SERVICE INSTALLATION EACH 80400100	GROUNDING ELECTRODE BELOW GRADE EACH 80600200	CONDUIT PUSHED 3" DIA. INT. METAL FOOT 81020700	CONDUIT ENCASED 2" DIA. PVC 2x1 FOOT 81025300	TRENCH AND BACKFILL ELECTRICAL WORK FOOT 81500200	UNIT DUCT 2 #2 XLP 1/4" POLY. FOOT 81600515	LUMINAIRE SODIUM VAP. HIGH MAST 400 WATT EACH 82105600	LUMINAIRE SODIUM VAP. HIGH MAST 750 WATT EACH 82105700	LIGHTING CONTROLLER CB-RCS 60A 480 VOLT EACH 82500525	LIGHT TOWER 100 FT LUMINAIRE MT. -4 EACH 83502300	LIGHT TOWER 150 FT LUMINAIRE MT. -6 EACH 83507800	LIGHT TOWER FOUNDATION 48" DIA. FOOT 83700300	LIGHT TOWER FOUNDATION 54" DIA. FOOT 83700350
F.A.I. 80														
820+60.23, 63' LT TO 64' RT				1										
F.A.P. 623 (SENECA ROAD)														
12+94.20, 34' LT TO 34' RT				1										
13+00.70 TO 14+05.05 LT							1							
14+59.28 TO 23+73.25 LT							1							
14+59.31, 116.08' LT									1					
15+05.11, 55.96' LT								4		1		13		
23+73.25, 55.39' LT								4		1		13		
RAMP C														
205+57.60, 31.82' RT									5		1			18
205+57.60 TO 220+36.68 RT							1							
220+00 TO 220+38.03 LT		1												
220+38.03, 18.0' LT TO 18.0' RT								36						
RAMP D														
250+07.96 TO 265+19.78 RT							1							
265+19.78, 32.10' RT									5		1			18
TOTALS		1		2	36		4	8	10	1	2	2	26	36

LIGHTING REMOVAL SCHEDULE

LOCATION	REMOVAL EX. LIGHTING UNIT SALVAGE EACH 84200500	LIGHTING FOUNDATION REMOVAL, PARTIAL EACH 84200705	REMOVAL LIGHTING CONTROLLER EACH 84500110	REMOVAL ELECTRIC INSTALLATION EACH 84500120	REMOVAL LIGHTING CONTROLLER FOUNDATION EACH 81400130	REMOVAL LIGHT TOWER EACH
F.A.P. 623 (SENECA ROAD)						
10+80.82, 63.14' LT				1		
10+93.52, 63.39' LT			1		1	
15+05.11, 55.96' LT						
15+22.08, 41.12' LT	4	1				1
23+62.83, 40.63' LT	4	1				1
RAMP C						
209+74.77, 23.84' RT	4	1				1
RAMP D						
260+88.30, 28.90' RT	4	1				1
TOTALS	16	4	1	1	1	4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**I-80 (F.A.I. 80) AT
 SENECA ROAD (F.A.P. 623)
 GRUNDY COUNTY**
 SCHEDULE OF QUANTITIES
 SCALE: N.T.S. DRAWN BY NMR/BJG
 DATE 10/14/05 CHECKED BY DJL/JPL