

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	CHAMPAIGN	115	7

URBAN FAI-74 MULTILANE ROADWAY IMPROVEMENTS							
BRIDGE REPAIR	90% FEDERAL 10% STATE FAI-74 I000						
90% FED 10% STATE SFTY-2A							
SN 010-0021	MAIN LINE	I-57 RAMP	PROSPECT RAMP	NEIL ST RAMP	LINCOLN AVE RAMP	U. S. 45 RAMP	U. S. 150 RAMP

CONSTRUCTION TYPE CODE

LOCATION OF WORK

CODE NO	ITEM	UNIT	QUANTITY	SN 010-0021	MAIN LINE	I-57 RAMP	PROSPECT RAMP	NEIL ST RAMP	LINCOLN AVE RAMP	U. S. 45 RAMP	U. S. 150 RAMP
60100060	CONCRETE HEADWALL FOR PIPE DRAIN	EACH	1.0	0.0	0.0	0.0	0.0	0.0	1.0 +	0.0	0.0
60107600	PIPE UNDERDRAINS, 4"	FOOT	550.0	0.0	0.0	0.0	0.0	0.0	550.0 +	0.0	0.0
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	20.0	0.0	0.0	0.0	0.0	0.0	20.0 +	0.0	0.0
60260100	INLETS ADJUSTMENT	EACH	8.0	4.0	4.0	0.0	0.0	0.0	0.0	0.0	0.0
60262700	INLETS TO BE RECONSTRUCTED	EACH	2.0	0.0	0.0	0.0	0.0	0.0	2.0 +	0.0	0.0
60300105	ADJUST FRAMES AND GRATES	EACH	7.0	0.0	7.0	0.0	0.0	0.0	0.0	0.0	0.0
60605000	COMBINATION CONC. CURB AND GUTTER, TY B-6.24	FOOT	730.0	0.0	0.0	0.0	0.0	0.0	730.0 +	0.0	0.0
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	330.0	0.0	330.0	0.0	0.0	0.0	0.0	0.0	0.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	31.0	0.0	31.0	0.0	0.0	0.0	0.0	0.0	0.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	14.0	0.0	14.0	0.0	0.0	0.0	0.0	0.0	0.0
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	19.0	0.0	19.0	0.0	0.0	0.0	0.0	0.0	0.0
* 63200310	GUARDRAIL REMOVAL	FOOT	1,386.0	0.0	1,386.0	0.0	0.0	0.0	0.0	0.0	0.0
* 63300205	REMOVE AND REINSTALL EXISTING STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	41.0	41.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
64200105	SHOULDER RUMBLE STRIP	FOOT	132,751.0	0.0	132,751.0	0.0	0.0	0.0	0.0	0.0	0.0
66410400	CHAIN LINK FENCE REMOVE AND REERECT	FOOT	39.0	39.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	10.0	0.0	10.0	0.0	0.0	0.0	0.0	0.0	0.0
67100100	MOBILIZATION	L SUM	1.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0	0.0
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0	0.0
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	28.0	1.0	0.0	8.0	3.0	4.0	4.0	4.0	4.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	1.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1.0	1.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
70101800	TRAFFIC CONTROL AND PROTECTION, SPECIAL	L SUM	1.0	1.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0	0.0	0.0	0.0	0.0	0.0	1.0	0.0	0.0
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	0.0	0.0	0.0	0.0	0.0	1.0	0.0	0.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25.0	10.0	0.0	0.0	0.0	0.0	15.0 +	0.0	0.0
70300100	SHORT TERM PAVMENT MARKING	FOOT	44,117.0	1,373.0	30,613.0	2,369.0	1,638.0	1,911.0	2,013.0	1,722.0	2,478.0
70300610	TEMPORARY PAVEMENT MARKINGS, LETTERS AND SYMBOLS	SQ FT	780.0	0.0	0.0	0.0	109.2	343.2	234.0	93.6	0.0
70300625	TEMPORARY PAINT PAVEMENT MARKING, LINE 4"	FOOT	178,331.0	45,359.0	85,821.0	15,644.0	4,670.0	5,627.0	6,781.0	7,547.0	6,882.0
70300735	TEMPORARY PAINT PAVEMENT MARKING 6" WHITE	FOOT	511.0	0.0	0.0	0.0	286.0	0.0	133.0	92.0	0.0
70300740	TEMPORARY PAINT PAVEMENT MARKING 8" WHITE	FOOT	39,874.0	0.0	17,805.0	5,944.0	2,176.0	4,555.0	4,478.0	3,214.0	1,702.0
70300745	TEMPORARY PAINT PAVEMENT MARKING 12" WHITE	FOOT	2,253.0	0.0	0.0	0.0	541.0	763.0	661.0	288.0	0.0
70300760	TEMPORARY PAINT PAVEMENT MARKING 24" WHITE	FOOT	529.0	0.0	0.0	0.0	59.0	162.0	135.0	173.0	0.0
70300825	TEMPORARY PAINT PAVEMENT MARKING 4" YELLOW	FOOT	102,837.0	0.0	78,578.0	7,835.0	1,984.0	2,347.0	3,083.0	4,341.0	4,669.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22,243.0	15,119.0	7,124.0	0.0	0.0	0.0	0.0	0.0	0.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	875.0	875.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	825.0	825.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	3.0	0.0	0.0	0.0	0.0	0.0	3.0 +	0.0	0.0
*78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, LINE 4"	FOOT	24,237.0	0.0	23,097.0	0.0	160.0	320.0	260.0	400.0	0.0
*78008300	POLYUREA PAVEMENT MARKING, TYPE II - LETTERS & SYMBOLS	SQ FT	780.0	0.0	0.0	0.0	109.0	343.0	234.0	94.0	0.0
*78008310	POLYUREA PAVEMENT MARKING, TYPE II, LINE 4"	FOOT	214,353.0	3,710.0	141,303.0	23,479.0	6,494.0	7,654.0	8,674.0	11,488.0	11,551.0
*78008330	POLYUREA PAVEMENT MARKING, TYPE II - LINE 6"	FOOT	511.0	0.0	0.0	0.0	286.0	0.0	133.0	92.0	0.0
*78008340	POLYUREA PAVEMENT MARKING, TYPE II, LINE 8"	FOOT	39,874.0	0.0	17,805.0	5,944.0	2,176.0	4,555.0	4,478.0	3,214.0	1,702.0
*78008350	POLYUREA PAVEMENT MARKING, TYPE II - LINE 12"	FOOT	2,253.0	0.0	0.0	0.0	541.0	763.0	661.0	288.0	0.0

* SPECIALTY ITEMS Δ SFTY-3N ○ Y031-1F (HS FUNDS) + I000-1A (HS FUNDS)