

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	(122BR)BR	VERMILION	25	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE X080-2A
20200100	EARTH EXCAVATION	CU YD	105	105
20400800	FURNISHED EXCAVATION	CU YD	86	86
25000210	SEEDING CLASS 2A	ACRE	0.75	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	68
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68	68
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	68
25100115	MULCH, METHOD 2	ACRE	0.75	0.75
25100630	EROSION CONTROL BLANKET	SQ YD	833	833
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	80
28000300	TEMPORARY DITCH CHECKS	EACH	1	1
28000400	PERIMETER EROSION BARRIER	FOOT	80	80
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	34	34
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174
44000030	BITUMINOUS SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	290	290
48101200	AGGREGATE SHOULDERS, TYPE B	TON	122	122
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
50102400	CONCRETE REMOVAL	CU YD	0.5	0.5
50300225	CONCRETE STRUCTURES	CU YD	0.5	0.5
50300260	BRIDGE DECK GROOVING	SQ YD	134	134
50300300	PROTECTIVE COAT	SQ YD	147	147
X5030305	CONCRETE WEARING SURFACE 5"	SQ YD	144	144
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17' DEPTH)	SQ FT	1230	1230

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE X080-2A
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1920	1920
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	75	75
51500100	NAME PLATES	EACH	1	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	500.0	500.0
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE I, SPECIAL (TANGENT)	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	456	456
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4'	FOOT	450	450
* 78200400	GUARDRAIL REFLECTORS	EACH	10	10
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50	TON	45	45

* DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES
DATE 6/05		DRAWN BY NJV CHECKED BY SJK