CONTRACT NO. 76953

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
604 & 789	103RS-1, 5GRS-2	MADISON	8	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: LOC. #1 RURAL I000-2A 90% FED. 10% STATE	LOC. #2 URBAN I000-2A 90% FED. 10% STATE	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	29	29		
25000200	SEEDING, CLASS 2	ACRE	0.2	0.2		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18		
25100115	MULCH, METHOD 2	ACRE	0.2	0.2		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.9		1.9	
40600300	AGGREGATE (PRIME COAT)	TON	8.9		8.9	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	48		48	
40600990	TEMPORARY RAMP	SQ YD	60		60	
44000003	BITUMINOUS SURFACE REMOVAL 3/4"	SQ YD	5191		5191	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	968	968		
60255500	MANHOLES TO BE ADJUSTED	EACH	2		2	
64200105	SHOULDER RUMBLE STRIP	FOOT	2904	2904		
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14804		14804	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	162		162	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2691		2691	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7402		7402	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	81		81	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	34		34	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	34		34	
X4066446	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N70	TON	478		478	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	290		290	
X7030200	SHORT-TERM PAVEMENT MARKING (SPECIAL)	FOOT	555		555	

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: LOC. #1 RURAL I000-2A 90% FED. 10% STATE	LOC. #2 RURAL I000-2A 90% FED. 10% STATE	

*SPECIALTY ITEMS

PLOT DATE = 10/25/2005
FILE NAME = c:\pwworking\d-district\e89485\plan\plnd894850.dgn
PLOT SCALE = 49.9999 ' / IN.
REFERENCE = REF