

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-1A 90% FED. 10% STATE	-----	-----
20200100	EARTH EXCAVATION	CU YD	752	752		
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	40	40		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40	40		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	40	40		
25100115	MULCH, METHOD 2	ACRE	1	1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250	250		
28000300	TEMPORARY DITCH CHECKS	EACH	10	10		
28000400	PERIMETER EROSION BARRIER	FOOT	400	400		
28000500	INLET AND PIPE PROTECTION	EACH	3	3		
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	1035	1035		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	34	34		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	39	39		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.4	1.4		
40600300	AGGREGATE (PRIME COAT)	TON	11	11		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174		
40600990	TEMPORARY RAMP	SQ YD	49	49		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	13	13		
44000100	PAVEMENT REMOVAL	SQ YD	135	135		
44004250	PAVED SHOULDER REMOVAL	SQ YD	610	610		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2037	2037		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	50	50		
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	91	91		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	341	341		
50105220	PIPE CULVERT REMOVAL	FOOT	25	25		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	35	35		
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	540	540		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-1A 90% FED. 10% STATE	-----	-----
63200310	GUARDRAIL REMOVAL	FOOT	740	740		
66101120	BITUMINOUS SHOULDER CURB	FOOT	606	606		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	170	170		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	32	32		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5686	5686		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	160	160		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	29	29		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	57	57		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	32	32		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5686	5686		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	160	160		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	29	29		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	64	64		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	35	35		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	28	28		
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	1035	1035		
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	357	357		
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	57	57		

* SPECIALTY ITEMS