

SUMMARY OF QUANTITIES							
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	SIDEWALK IL ROUTE 53 SFTY-1B	TRAFFIC SIGNALS IL ROUTE 53 Y031-1F	SIDEWALK OGDEN AVENUE SFTY-1B	SIDEWALK OFF-SITE COMP. STORAGE SITE SFTY-1B
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	21	21			
20101000	TEMPORARY FENCE	FOOT	902	902			
20101200	TREE ROOT PRUNING	EACH	28	28			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,433	1,211		80	142
20400800	FURNISHED EXCAVATION	CU YD	221	221			
20800150	TRENCH BACKFILL	CU YD	6	6			
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	3.70	3.20		0.08	0.42
25200200	SUPPLEMENTAL WATERING	UNIT	344	326		18	
28000400	PERIMETER EROSION BARRIER	FOOT	1,720	1,510			210
28000510	INLET FILTERS	EACH	23	23			
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	675	675			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	480	480			
42001300	PROTECTIVE COAT	SQ YD	3,980	3,800		180	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	33,302	31,702		1,600	
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	705	705			
42400800	DETECTABLE WARNINGS	SQ FT	550	550			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	325	325			
44000300	CURB REMOVAL	FOOT	30	30			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	413	413			
44000600	SIDEWALK REMOVAL	SQ FT	847	847			
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	320	320			
51000105	PIPE HANDRAIL	FOOT	215	215			
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	4	3		1	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1			
60251200	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	3	3			
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	3		1	
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60500060	REMOVING INLETS	EACH	1	1			
60600605	CONCRETE CURB, TYPE B	FOOT	30	30			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	140	140			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	273	273			
67100100	MOBILIZATION	L SUM	1	1			
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1			
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,360	1,360			
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	438	438			
78300105	PAVEMENT MARKING REMOVAL	FOOT	38.67	38.67			

SUMMARY OF QUANTITIES							
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	SIDEWALK IL ROUTE 53 SFTY-1B	TRAFFIC SIGNALS IL ROUTE 53 Y031-1F	SIDEWALK OGDEN AVENUE SFTY-1B	SIDEWALK OFF-SITE COMP. STORAGE SITE SFTY-1B
81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	20		20		
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	45		45		
81400115	HANDHOLE TO BE ADJUSTED	EACH	11		11		
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	20		20		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	5		5		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,933		1,933		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3,389		3,389		
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2		2		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8		
87900200	DRILL EXISTING HANDHOLE	EACH	2		2		
88000160	SIGNAL HEAD, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3		3		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	10		10		
89502200	MODIFY EXISTING CONTROLLER	EACH	5		5		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3		3		
XX002010	MODULAR CONCRETE RETAINING WALL	SQ FT	2,306	2,034			272
XX004093	CONCRETE SLOPEWALL REMOVAL	SQ FT	515	515			
XX004833	STABILIZED DRIVEWAYS SUPERPAVE 7"	SQ YD	265	265			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	23	23			
X8810610	PEDESTRIAN SIGNAL HEAD, L.E.D. 1-FACE, BRACKET MOUNTED	EACH	9		9		
X8810620	PEDESTRIAN SIGNAL HEAD, L.E.D. 2-FACE, BRACKET MOUNTED	EACH	4		4		
XX006429	SIDEWALK, SPECIAL	SQ FT	675	675			
XX006430	CLASS D PATCHES SUPERPAVE, TYPE 1 2 INCH	SQ YD	50	50			
XX006431	STORM SEWERS, PVC 12"	FOOT	25	25			
Z0017400	DRAINAGE AND UTILITY STRUCTURE TO BE ADJUSTED	EACH	19	18			1
X0332671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	8	8			

* - DENOTES SPECIALTY ITEMS

DRAWN SMP
CHECKED BDH

DATE... 9/21/05...
SCALE... N/A...

JAMES J. BENES & ASSOCIATES, INC.
950 Warrenville Road, Suite 101, Lisle, Illinois 60532
Tel. (630) 719-7570 • Fax (630) 719-7589



VILLAGE OF LISLE
IL ROUTE 53 SIDEWALK IMPROVEMENTS

REVISIONS		
NO.	DATE	DESCRIPTION

SUMMARY OF QUANTITIES

DRAWING NO.
3 OF 46