

TREE REMOVAL (6 TO 15 UNIT DIA)		
STATION	OFFSET (FOOT)	QUANTITY (UNIT)
IL-53		
12+18	10' LT	9
18+15	12' LT	12
TOTAL QUANTITY =		21

DRAINAGE AND UTILITY STRUCTURES TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
IL-53		
8+26	6' LT	1
9+22	2' LT	1
10+70	5' LT	1
12+28	5' LT	1
14+26	3' LT	1
16+20	4' LT	1
18+27	6' LT	1
20+11	7' LT	1
21+52	1' LT	1
27+57	11' RT	1
29+08	17' RT	1
30+00	14' RT	1
33+05	12' RT	1
52+15	3' RT	1
53+97	5' RT	1
68+48	20' RT	1
69+43	13' RT	1
70+91	7' RT	1
OGDEN AVE.		
103+17	20' RT	1
TOTAL QUANTITY =		19

HANDHOLES TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
IL-53		
3+35	1' RT	1
5+81	1' RT	1
22+34	2' RT	1
51+49	1' RT	1
53+99	10' RT	1
65+80	17' RT	1
71+80	1' RT	1
73+29	1' RT	1
75+42	102' LT	1
76+00	14' RT	1
77+10	4' RT	1
TOTAL QUANTITY =		11

MANHOLES TO BE RECONSTRUCTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
IL-53		
33+85	12' RT	1
49+81	18' RT	1
62+46	7' RT	1
OGDEN AVE.		
102+80	10' RT	1
TOTAL QUANTITY =		4

EARTHWORK		
LOCATION	REMOVAL & DISPOSAL OF UNSUITABLE MAT.* (CU YD)	FURNISHED EXCAVATION** (CU YD)
IL-53: ROLLING RD. (1+70) TO OMISSION (39+00)	732	143
IL-53: OMISSION(47+50) TO WARRENVILLE RD.(78+00)	479	78
OGDEN AVENUE	80	0
OFF-SITE COMP. STORAGE SITE	142	0
TOTAL QUANTITY =	1,433	221

MANHOLE TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID		
STATION	OFFSET (FEET)	QUANTITY (EACH)
IL-53		
1+76	28' RT	1
TOTAL QUANTITY =		1

REMOVING INLETS		
STATION	OFFSET (FEET)	QUANTITY (EACH)
IL-53		
37+30	10' RT	1
TOTAL QUANTITY =		1

CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID		
STATION	OFFSET (FEET)	QUANTITY (EACH)
IL-53		
33+65	18' RT	1
60+35	14' RT	1
61+35	14' RT	1
TOTAL QUANTITY =		3

FIRE HYDRANTS TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
IL-53		
8+60	13' LT	1
17+60	8' LT	1
68+67	15' RT	1
OGDEN AVE.		
103+16	12' RT	1
TOTAL QUANTITY =		4

*ALL CUT MATERIAL SHALL BE HAULED OFF SITE DUE TO NO ONSITE STORAGE LOCATIONS.
 **ALL FILL MATERIAL (EMBANKMENT) SHALL BE BROUGHT IN FROM OFFSITE LOCATION, SINCE ON SITE EXCAVATED MATERIAL MUST BE HAULED OFF SITE.

DRAWN SMP
 CHECKED BDH

DATE .. 9/21/05 ..
 SCALE .. N/A ..

JAMES J. BENES & ASSOCIATES, INC.
 950 Warrenville Road, Suite 101, Lisle, Illinois 60532
 Tel. (630) 719-7570 • Fax (630) 719-7589



VILLAGE OF LISLE
IL ROUTE 53 SIDEWALK IMPROVEMENTS

REVISIONS		
NO.	DATE	DESCRIPTION

SCHEDULE OF QUANTITIES

DRAWING NO.
 4 OF 46