

ROUTE NO.	SECTION	COUNTY	SHEET	SHEET
F.A.U. 6385	00-00182-01-BR	McLEAN	33	3
FED. ROAD DIST. NO.		ILLINOIS PROJECT: MPO-822743		

CONTRACT NO. 87269

LOCATION	ROADWAY SCHEDULE														
	BRIDGE APPROACH PAVEMENT	FLEXIBLE PAVEMENT CONNECTOR	SUBBASE GRAN. MATL. TYPE A	BITUMIONUS SURF CSE SUPERPAVE MIX "D", N50	BITUMIONUS BINDER CSE SUPERPAVE IL-19.0 N50	LEVELING BINDER MACHINE METHOD SUPERPAVE N50	BITUMIONUS SHOULDER SUPERPAVE	AGGREGATE SHOULDER TYPE B	AGGREGATE BASE CSE SPECIAL	AGGREGATE BASE CSE TYPE B	BITUMIONUS SURFACE REMOVAL BUTT-JOINT	BITUMIONUS MATERIAL PRIME COAT	AREA REFLECTIVE CRACK CONTROL SYSTEM A	GUTTER REMOVAL	PAVEMENT REMOVAL
	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON	SQ YD	GAL	SQ YD	FOOT	SQ YD
STA 817+50 TO STA 819+37.30	141	28	151	34	45	17	68	97			213	40	403		122
STA 821+05.35 TO STA 822+50	141	28	151	32	43	23	22	55	57	37	213	62	290	31	156
W GRAHAM ST.				16	27				121	73		67		124	222
TOTAL	282	56	302	82	115	40	90	152	178	110	426	169	693	155	500

LOCATION	GUARDRAIL SCHEDULE					
	STEEL PLATE BEAM GUARDRAIL TYPE A	TRAFFIC BARRIER TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TYPE 6	TRAFFIC BARRIER TYPE 6 SPECIAL	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL REFLECTORS
	FOOT	EACH	EACH	EACH	EACH	EACH
RT. STA. 817+95.25 TO RT. STA. 819+53.40	75	1	1		1	
LT. STA. 818+17.57 TO LT. STA. 819+25.72	25	1	1		1	
LT. STA. 820+87.86 TO LT. STA. 821+71.01		1		1	1	
RT. STA. 821+17.33 TO RT. STA. 822+25.48	25	1	1		1	
RT. STA. 817+95.25 TO RT. STA. 822+25.48						6
LT. STA. 818+17.57 TO LT. STA. 821+71.01						5
TOTAL	125	4	3	1	4	11

CURB AND GUTTER TYPE B-6.24 SCHEDULE	
LOCATION	FOOT
CH 70	
LT. STA. 821+81.00 TO LT. STA. 821+88.00	7
WEST GRAHAM ST	
RT. STA. 10+50.00 TO RT. STA. 10+57.34	7
RT. STA. 10+57.34 TO RT. STA. 1087.84	48
LT. STA. 10+50.00 TO LT. STA. 10+92.98	43
LT. STA. 10+92.98 TO LT. STA. 11+22.30	37
TOTAL	142

TREE REMOVAL (6 TO 15 UNITS)	
LOCATION	FOOT
CH 70	
40' LT. STA. 817+88	6
43' LT. STA. 818+53	6
37' LT. STA. 818+68	12
52' LT. STA. 819+30	8
52' LT. STA. 819+40	6
52' LT. STA. 819+40	6
26' RT. STA. 819+40	8
26' RT. STA. 819+40	8
26' RT. STA. 819+40	8
26' RT. STA. 819+40	8
34' RT. STA. 819+52	8
34' RT. STA. 819+52	8
34' RT. STA. 819+52	8
43' RT. STA. 819+54	8
43' RT. STA. 819+54	8
TOTAL	116

LOCATION	SEEDING SCHEDULE					
	SEEDING CLASS 2A SPECIAL ACRES	NITROGEN FERTILIZER NUTRIENT 90 LBS/ACRE	PHOSPHORUS FERTILIZER NUTRIENT 90 LBS/ACRE	POTASSIUM FERTILIZER NUTRIENT 90 LBS/ACRE	AGRICULTURAL GROUND LIMESTONE 90 LBS/ACRE	MULCH METHOD 1 90 LBS/ACRE
	ACRES	LBS	LBS	LBS	TONS	TONS
LT STA 817+50 TO LT STA 819+25	0.11	10	10	10	10	0.22
RT STA 817+50 TO RT STA 819+50	0.05	5	5	5	5	0.1
LT STA 820+85 TO LT STA 822+50	0.07	6	6	6	6	0.14
RT STA 821+20 TO RT STA 822+50	0.05	5	5	5	5	0.1
TOTAL	0.28	26*	26*	26*	26*	0.56*

GUTTER REMOVAL	
LOCATION	FOOT
CH 70	
LT. STA. 820+80.00 TO LT. STA. 821+11.00	31
WEST GRAHAM ST	
LT. STA. 11+19.00 TO LT. STA. 10+50.00	54
RT. STA. 10+97.00 TO RT. STA. 10+50.00	70
TOTAL	155

TREE REMOVAL (OVER 15 UNITS)	
LOCATION	FOOT
CH 70	
48' LT. STA. 820+05	18
40' RT. STA. 821+06	14
TOTAL	32

EROSION CONTROL BLANKET	
LOCATION	SQ YD
CH 70	
LT. STA. 818+00 TO LT. STA. 819+25	369
RT. STA. 817+50 TO RT. STA. 819+53	219
RT. STA. 821+17 TO RT. STA. 822+50	305
LT. STA. 820+87 TO LT. STA. 819+25	28
TOTAL	921

LOCATION	EARTHWORK SCHEDULE					
	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE(25%)	% USED	EARTH EXCAVATION AVAILABLE CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
MAINLINE C.H. 70						
STA. 817+50 TO STA. 819+37.31	71	53	100.00%	53	404	-351
STA. 821+05.37 TO STA. 822+50	79	59	100.00%	59	282	-223
S.R. WEST GRAHAM	39	29	100.00%	29	10	19
CHANNEL EXCAVATION	220	165	70.00%	116	0	116
TOTAL	409	306		257	696	-440

HLR
 Rice, Berry and Associates
 A Division of Hampton, Lenzini and Renwick, Inc.
 Civil & Structural Engineers
 3085 Stevenson Drive
 Suite 201
 Springfield, Illinois 62703
 217-546-3400
 P.O. Box 1036
 DuQuoin, Illinois 62832
 618-790-4637
 Account Number 12-59-0033-1
 Date: 11/15/05
 DESIGNED: L.F.S. CHECKED: S.W.M. DRAWN: T.W.K.

SCHEDULE OF QUANTITIES
 SECTION 00-00182-01-BR
 F.A.U. 6385 / C.H. 70
 McLEAN COUNTY