



ROUTE NO.	SECTION	COUNTY	SHEET NO.	TOTAL SHEETS
F.A.U. 6385	00-00182-01-BR	McLEAN	33	4
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT: BRN-8027143	

CONTRACT NO. 87269



EXISTING TYPICAL SECTION
STA. 817+50.00 TO STA. 822+50.00




PROPOSED TYPICAL SECTION
STA. 817+50.00 TO STA. 819+01.29
STA. 821+41.38 TO STA. 822+50.00

- LEGEND**
- ① EXISTING BITUMINOUS PAVEMENT (3"±)
 - ② EXISTING PCC BASE 8"
 - ③ EXISTING SHOULDER
 - ④ EXISTING GUTTER
 - ⑤ BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX D, N50 (1 1/2" THICKNESS MIN.)
 - ⑥ BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE IL 19, N50 (2" THICKNESS)
 - ⑦ BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE IL 19, N50 (2.5" THICKNESS)
 - ⑧ LEVELING BINDER (MACHINE METHOD) 1/2" MINIMUM THICKNESS
 - ⑨ AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A
 - ⑩ AGGREGATE BASE COURSE, TYPE B 6"
 - ⑪ AGGREGATE BASE COURSE SPECIAL 6"
 - ⑫ BITUMINOUS SURFACE REMOVAL, BUTT-JOINT
 - ⑬ BITUMINOUS MATERIALS (PRIME COAT)
 - ⑭ BITUMINOUS SHOULDERS, SUPERPAVE 8"
 - ⑮ AGGREGATE SHOULDERS 6"
 - ⑯ BRIDGE APPROACH PAVEMENT
 - ⑰ BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)
 - ⑱ SEE STD 420401 FOR SUB-BASE GRANULAR MATERIAL
 - ⑲ INCLUDED IN THE COST OF BRIDGE APPROACH PAVEMENT
 - ⑳ COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
 - ㉑ STEEL PLATE BEAM GUARDRAIL
 - ㉒ TRAFFIC BARRIER TERMINAL TYPE 6
 - ㉓ TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL
 - ㉔ TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL

NOTES

- 1) COST OF SAWCUT SHALL BE INCLUDED IN THE UNIT COST BID FOR BITUMINOUS SURFACE REMOVAL.
- 2) CURB IS NOT REQUIRED ALONG THE EAST EDGE OF THE SOUTH BRIDGE APPROACH PAVEMENT SLAB.
- 3) REFLECTIVE CRACK CONTROL TREATMENT SHALL BE APPLIED AFTER LEVELING BINDER



TYPICAL CROSS SECTION
STA. 819+01.29 TO STA. 819+07.27 (FLEXIBLE PVT. CONNECTOR)
STA. 819+07.27 TO STA. 819+37.30 (BRIDGE APPR. PVT.)
STA. 821+05.38 TO STA. 82+35.35 (BRIDGE APPR. PVT.)
STA. 821+35.35 TO STA. 821+41.38 (FLEXIBLE PVT. CONNECTOR)

SUGGESTED FILL SECTION
CONSTRUCT AS SHOWN IN
STATION CROSS SECTIONS

SUGGESTED CUT SECTION
CONSTRUCT AS SHOWN IN
STATION CROSS SECTIONS

HLR
Rice, Berry and Associates
A Division of Hampton,
Lenzini and Renwick, Inc.
Civil & Structural Engineers
3085 Stevenson Drive
Suite 201
Springfield, Illinois 62703
217-546-3400
P.O. Box 1036
DuQuoin, Illinois 62832
618-790-4637
Account Number
12-59-0033-1
Date: 11/15/05
DESIGNED: L.F.S. CHECKED: S.W.M. DRAWN: D.B.

TYPICAL CROSS SECTIONS
SECTION 00-00182-01-BR
F.A.U. 6385 / C.H. 70
McLEAN COUNTY