

F.A. RTE. 6708
SECTION 03-0010-00-TL
COUNTY: TAZEWELL
CONTRACT NO. 89353
CAT NO. 032923-00

EARTH EXCAVATION SCHEDULE	
STATION	QUANTITY (CU YD)
PARK AVE.	
STA. 5+13.00 TO STA. 7+3.35	91
STA. 7+55.95 TO STA. 9+68.73	78
STA. 10+30.63 TO STA. 13+27.07	97
STA. 13+74.98 TO STA. 15+51.24	54
STA. 15+22.24 TO STA. 15+58.26	19
14TH ST.	
STA. 24+34.54 TO STA. 26+36.79 RT.	19
TOTAL =	358

SEEDING, CLASS 1A SCHEDULE	
STATION	QUANTITY (ACRE)
14TH ST.	
STA. 24+35 RT TO STA. 24+54 RT	0.002
STA. 24+66 RT TO STA. 25+90 RT	0.025
PARK AVE.	
STA. 10+28 RT TO STA. 13+38 RT	0.08
TOTAL =	0.09

PCC BASE COURSE 6" SCHEDULE	
STATION	QUANTITY (SQ YD)
PARK AVE.	
STA. 5+13.00 TO STA. 7+3.35	205
STA. 7+55.95 TO STA. 9+68.73	177
STA. 10+30.63 TO STA. 13+27.07	218
STA. 13+74.98 TO STA. 15+51.24	122
STA. 15+22.24 TO STA. 15+58.26	43
TOTAL =	765

BITUMINOUS CONCRETE BINDER COURSE SCHEDULE	
STATION	QUANTITY (TON)
STA. 5+13.00 TO STA. 7+03.35	42
STA. 7+55.95 TO STA. 9+68.73	47
STA. 10+30.63 TO STA. 13+27.07	66
STA. 13+74.98 TO STA. 15+51.24	39
RIGHT TURN LANE	11
TOTAL =	205

BITUMINOUS CONCRETE SURFACE COURSE SCHEDULE	
LOCATION	QUANTITY (TON)
PARK AVENUE	554
14TH STREET	60
INTERSECTION	78
MEDIANS (SUBTRACTED)	70
TOTAL =	622

PCC SIDEWALK 4" SCHEDULE	
STATION	QUANTITY (SQ FT)
PARK AVE.	
STA. 10+21.27 TO STA. 13+37.33 RT.	1669
TOTAL =	1669

BITUMINOUS SURFACE REMOVAL, 1.5" SCHEDULE	
LOCATION	QUANTITY (SQ YD)
PARK AVENUE	5666
14TH STREET	655
INTERSECTION OF PARK AND 14TH	909
MEDIANS (SUBTRACTED)	808
TOTAL =	6422

BITUMINOUS SURFACE REMOVAL, 3.5" SCHEDULE	
STATION	QUANTITY (SQ YD)
PARK AVE.	
STA. 5+13.00 TO STA. 7+3.35	340
STA. 7+55.95 TO STA. 9+68.73	325
STA. 10+30.63 TO STA. 13+27.07	422
STA. 13+74.98 TO STA. 15+51.24	232
STA. 15+51.22 TO STA. 15+71.95	16
14TH ST.	
STA. 24+34.54 TO STA. 26+36.79	111
TOTAL =	1446

COMB. CURB & GUTTER REMOVAL SCHEDULE	
STATION RANGE	QUANTITY (FT.)
PARK AVE.	
STA. 5+13.00 TO STA. 7+3.35	391
STA. 7+55.95 TO STA. 9+68.73	433
STA. 10+30.63 TO STA. 13+27.07	600
STA. 13+74.98 TO STA. 15+51.24	357
STA. 15+51.22 TO STA. 15+71.95	84
STA. 10+21.27 TO STA. 10+55.88	57
14TH ST.	
STA. 24+34.54 TO STA. 26+15.97	202
TOTAL =	2124

SIDEWALK REMOVAL SCHEDULE	
STATION	QUANTITY (SQ FT)
PARK AVE.	
STA. 10+21.27 TO STA. 10+55.88 RT.	220
11+4.47 RT.	63
11+55.56 RT.	93
12+54.54 RT.	58
13+2.66 RT.	39
TOTAL =	473

STRIP REFLECTIVE CRACK CONTROL TREATMENT, 2'(WIDE) SCHEDULE	
STATION RANGE	QUANTITY (FT.)
PARK AVE.	
STA. 5+13.00 TO STA. 7+3.35	391
STA. 7+55.95 TO STA. 9+68.73	433
STA. 10+30.63 TO STA. 13+27.07	600
STA. 13+74.98 TO STA. 15+51.24	357
STA. 15+51.22 TO STA. 15+71.95	84
STA. 10+21.27 TO STA. 10+55.88	57
14TH ST.	
STA. 24+34.54 TO STA. 26+15.97	202
TOTAL =	2124


COMB. CURB & GUTTER B-6.12 SCHEDULE	
STATION RANGE	QUANTITY (FT.)
PARK AVE.	
STA. 15+22.24 TO STA. 15+58.26	128
14TH ST.	
STA. 24+34.54 TO STA. 26+15.97	201
TOTAL =	329

CONCRETE MEDIAN SURFACE 4" SCHEDULE	
STATION	QUANTITY (SQ FT)
PARK AVE.	
STA. 15+22.24 TO STA. 15+58.26	954
TOTAL =	954

SIGN PANEL SCHEDULE		
STATION	TYPE	QUANTITY (SQ. FT.)
PARK AVE.		
15+66.00, 28.00' RT.	NO LEFT TURN (R3-2)	4
TOTAL =		4

THERMOPLASTIC PAVE. MARKING, 4" SCHEDULE	
STATION RANGE	QUANTITY (FT.)
PARK AVE.	
STA. 5+51.10 TO STA. 8+50.00	124
STA. 5+20.88 TO STA. 9+54.56	434
STA. 5+31.10 TO STA. 9+54.85	1696
STA. 10+80.88 TO STA. 13+68.69	194
STA. 10+41.16 TO STA. 13+28.62	288
STA. 10+41.16 TO STA. 13+22.67	1174
STA. 13+92.69 TO STA. 14+72.77	168
STA. 13+80.07 TO STA. 14+60.96	87
14TH ST.	
STA. 23+47.32 TO STA. 25+91.49	488
STA. 23+49.84 TO STA. 24+34.54	86
STA. 26+88.83 TO STA. 29+21.74	687
TOTAL =	5426

REVISIONS		
NUMBER	BY	DATE



CITY OF PEKIN, IL
INTERSECTION RECONSTRUCTION
14TH ST. & PARK AVE.

SCHEDULE OF QUANTITIES

© Copyright 2011, Inc.

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613



DESIGN BY:	R.M.M.
DRAWN BY:	N.D.S.
CHECKED BY:	E.J.H.
APPROVED BY:	
DATE:	10/12/05
JOB No:	05069-02-00