

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	14 A
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	TRAFFIC SIGNS	HIGHWAY LIGHTING	IMPACT ATTENUATORS
				80% FEDERAL 10% STATE 10% LOCAL J000-2A	STA. 247+85.29 TO STA. 250+65.29 80% FEDERAL 10% STATE 10% LOCAL X281-2A	80% FEDERAL 10% STATE 10% LOCAL Y002-1C	80% FEDERAL 10% STATE 10% LOCAL Y030-1E	80% FEDERAL 10% STATE 10% LOCAL SFTY-3N
30200600	PROCESSING LIME MODIFIED SOILS 12"	SQ YD	77995	77,995				
30201400	WATER	UNIT	390.0	390.0				
30201500	LIME	TON	1754.9	1,754.9				
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	46912	46,912				
35100400	AGGREGATE BASE COURSE, TYPE A 5"	SQ YD	113	113				
35100900	AGGREGATE BASE COURSE, TYPE A 10"	SQ YD	3146	3,146				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1750	1,750				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	178	178				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3971	3,971				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	56.3	56.3				
40800030	AGGREGATE (PRIME COAT)	TON	1	1				
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	19	19				
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	20636	20,636				
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	20745	20,745				
42001300	PROTECTIVE COAT	SQ YD	55461	55,461				
• 42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	416		416			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	60		60			
• 44005000	STABILIZED SHOULDER REMOVAL	SQ YD	4254	4,254				
48100100	AGGREGATE SHOULDERS, TYPE A	TON	1245	1,245				
• 48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	8606	8,606				
• 48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	10726	10,726				
• 48202800	BITUMINOUS SHOULDERS SUPERPAVE 10"	SQ YD	344	344				
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	78	78				
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	10104	10,104				
• 50105220	PIPE CULVERT REMOVAL	FOOT	270	270				
50200100	STRUCTURE EXCAVATION	CU YD	613		613			
50300225	CONCRETE STRUCTURES	CU YD	198.4		198.4			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	578.3		578.3			

- SEE SPECIAL PROVISIONS
- QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE		
		SUMMARY OF QUANTITIES	
		FAI-57, FAS 642	
		SEC NO. 15-23K, 99-00124-02-PV	
		COLES COUNTY, ILLINOIS	
		SCALE: NOT TO SCALE	DRAWN BY KET
		DATE 08/09/2005	CHECKED BY SKM



08/09/2005
 KET 05/24/05
 D.P. 05/26/05
 IN 99-0055 OF S20280/CH/1/Sheet-602-02sum.qip
 REVIEWED SKM 06/01/05