

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	BRIDGE STA. 247+85.29 TO STA. 250+65.29		TRAFFIC SIGNS 80% FEDERAL 10% STATE 10% LOCAL Y002-1C	HIGHWAY LIGHTING 80% FEDERAL 10% STATE 10% LOCAL Y030-1E	IMPACT ATTENUATORS 80% FEDERAL 10% STATE 10% LOCAL SFTY-3N
				ROADWAY 80% FEDERAL 10% STATE 10% LOCAL J000-2A	80% FEDERAL 10% STATE 10% LOCAL X281-2A			
•• 61101013	STORM SEWER, PROTECTED, CLASS A, 12"	FOOT	150	150				
•• 61101026	STORM SEWER, PROTECTED, CLASS A, 24"	FOOT	150	150				
•• 61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5	5				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1387.5	1,387.5				
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2				
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4			
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	5	5				
63200310	GUARDRAIL REMOVAL	FOOT	404	404				
63500105	DELINEATORS	EACH	101	101				
• 63500310	REMOVE AND REINSTALL DELINEATORS	EACH	10	10				
66101120	BITUMINOUS SHOULDER CURB	FOOT	1224	1,224				
66201120	CONCRETE SHOULDER CURB	FOOT	90	90				
66500105	WOVEN WIRE FENCE 4'	FOOT	10759	10,759				
• 66502300	WOVEN WIRE FENCE REMOVAL	FOOT	7693	7,693				
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	96	96				
• 67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24				
• 67000600	ENGINEER'S FIELD LABORATORY	CAL MO	16	16				
• 67100100	MOBILIZATION	L SUM	1	1				
• 70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1	1				
• 70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1				
• 70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1				
• 70103800	TRAFFIC CONTROL (SPECIAL)	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	200	200				
△ 72000100	SIGN PANEL - TYPE 1	SQ FT	379.9			379.9		
△ 72000200	SIGN PANEL - TYPE 2	SQ FT	262.8			262.8		
△ 72000300	SIGN PANEL - TYPE 3	SQ FT	1007.0			1,007.0		
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	96			96		
△ 72700100	STRUCTURAL STEEL SIGN SUPPORT- BREAKAWAY	POUND	8394			8,394		
△ 72900100	METAL POST - TYPE A	FOOT	26			26		

- SEE SPECIAL PROVISIONS
- QUANTITY PARTIALLY OR WHOLLY ASSUMED FOR ESTABLISHMENT OF UNIT PRICE
- △ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAI-57, FAS 642  
 SEC NO. 15-23K, 99-00124-02-PV  
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE  
 DATE 08/09/2005  
 DRAWN BY KET  
 CHECKED BY SKM



LAYOUT	RET	08/24/05
DRAWN	D.P.	08/26/05
REVIEWED	SKM	08/07/05