

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	59
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STATION	RAMP A				I-57 S.B. EXISTING E.O.P.		NEUTRAL AREA		
	RAMP A ELEVATION	OFFSET TO PROPOSED LEFT E.O.P.	LEFT E.O.P. ELEVATION	RIGHT E.O. AGG. SHLDR ELEVATION	LEFT E.O.S. ELEVATION	OFFSET FROM RAMP A	SURVEYED ELEV.	OFFSET FROM RAMP A	ELEVATION
10+00.00	691.37			690.76		1.00	691.38		
10+25.00	691.41			691.03		2.34	691.45		
10+50.00	691.46			691.13		3.67	691.52		
10+75.00	691.50			691.18		5.01	691.58		
11+00.00	691.54			691.22		6.34	691.64		
11+25.00	691.59			691.27		7.68	691.71		
11+50.00	691.61			691.29		9.01	691.75		
11+75.00	691.58			691.26		10.35	691.74		
12+00.00	691.57			691.25		11.68	691.75		
12+25.00	691.57			691.25		13.02	691.77		
12+50.00	691.56			691.24		14.35	691.78		
12+75.00	691.53			691.21		15.69	691.77		
12+99.57	691.52	16.00	691.76	691.20		17.00	691.76		
13+25.00	691.51	16.00	691.75	691.19		18.36	691.75		
13+50.00	691.49	16.00	691.73	691.17		19.70	691.73		
13+75.00	691.45	16.00	691.69	691.13		21.03	691.69		
14+00.00	691.40	16.00	691.64	691.08		22.37	691.64	19.17	691.59
14+25.00	691.35	16.00	691.59	691.03		23.70	691.59	19.56	691.52
14+50.00	691.29	16.00	691.53	690.97		25.04	691.53	19.94	691.45
14+75.00	691.21	16.00	691.45	690.89		26.37	691.45	20.32	691.37
15+00.00	691.14	16.00	691.38	690.82		27.71	691.38	20.71	691.28
15+25.00	691.06	16.00	691.30	690.74		29.04	691.30	21.09	691.19
15+50.00	691.00	16.00	691.24	690.68		30.38	691.24	21.47	691.11
15+75.00	690.94	16.00	691.18	690.62		31.71	691.18	21.86	691.04
16+00.00	690.89	16.00	691.13	690.57		33.05	691.13	22.24	690.97
16+25.00	690.82	16.00	691.06	690.50		34.38	691.06	22.62	690.89
16+50.00	690.76	16.00	691.00	690.44		35.72	691.00	23.01	690.81
16+60.09	690.74	16.00	690.98	690.42		36.26	690.98	23.16	690.78
16+75.00	690.66	16.00	690.95	690.34	690.79	37.06	690.95		
17+00.00	690.51	16.00	690.89	690.19	690.73	38.39	690.89		
17+25.00	690.35	16.00	690.81	690.03	690.66	39.73	690.81		
17+50.00	690.18	16.00	690.73	689.86	690.58	41.06	690.73		
17+75.00	690.05	16.00	690.68	689.73	690.54	42.40	690.68		
18+00.00	689.90	16.00	690.62	689.54	690.48	43.73	690.62		
18+25.00	689.72	16.00	690.53	689.32	690.40	45.52	690.53		
18+50.00	689.57	16.00	690.46	689.12	690.34	48.10	690.46		
18+70.09	689.46	16.00	690.42	688.98	690.30	50.75	690.42		



LAYOUT: [P:\S\M\03\28\03] 07/13/2005
 DRAWN: JLW 04/28/03
 REVIEWED: SKM 11/22/04
 I:\97\JOBS\91\20286\Civil\Sheet\c-501A\mp.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 RAMP A TERMINAL DETAIL
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE
 DATE 07/13/2005

DRAWN BY JLW
 CHECKED BY SKM