

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
855	11B-1	WHITE	25	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		097-2013 X028-2A	SFTY-3N
20200100	EARTH EXCAVATION	CU YD	349	349	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	81	81	
20400800	FURNISHED EXCAVATION	CU YD	243	243	
25000200	SEEDING, CLASS 2	ACRE	0.3	0.3	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.5	0.5	
25100115	MULCH, METHOD 2	ACRE	0.3	0.3	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	26	26	
28000300	TEMPORARY DITCH CHECKS	EACH	4	4	
28100107	STONE RIPRAP, CLASS A4	SQ YD	369	369	
28200200	FILTER FABRIC	SQ YD	369	369	
35650700	BASE COURSE WIDENING	SQ YD	257	257	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	49	49	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	65	65	
44000100	PAVEMENT REMOVAL	SQ YD	124	124	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	130	130	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50800105	REINFORCEMENT BARS	POUND	37490	37490	
51205200	TEMPORARY SHEET PILING	SQ FT	565	565	
51401600	TEMPORARY BRIDGE RAIL	FOOT	50	50	
51500100	NAME PLATES	EACH	1	1	
54003000	CONCRETE BOX CULVERTS	CU YD	241.2	241.2	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	462.5	462.5	
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	12.5	12.5	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	79	79	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	
* 63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	2	2	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	76	76	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		097-2013 X028-2A	SFTY-3N
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	76	76	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	713	713	
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	360	360	
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	340	340	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1736	1736	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	193	193	
X0348700	AGGREGATE DITCH CHECK	EACH	1	1	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	5	5	
X4073161	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 14"	SQ YD	225	225	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	7	7	
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	1	1	
Z0002600	BAR SPLICERS	EACH	216	216	
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY