

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
855	118-1	WHITE	25	6
STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

PAVEMENT MARKING SCHEDULE

LOCATION	PAINT PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	SHORT TERM PAVEMENT MARKING FOOT	PAINT PAVEMENT MARKING LINE - 4" (WHITE) FOOT	PAINT PAVEMENT MARKING LINE - 4" (YELLOW) FOOT
SN 097-2013 STAGE I					
279+29.0 TO 282+02.0	22.8	91.0			
282+02.0 TO 284+24.0	92.5	148.0			
284+04.0 TO 287+02.0	23.2	92.7			
STAGE I TOTALS	138.0	332.0	0.0	0.0	0.0
SN 097-2013 STAGE II					
279+29.0 TO 282+09.0		120.3	28.0	560.0	70.0
282+09.0 TO 284+18.0	55.3	139.3	20.0	418.0	50.0
284+18.0 TO 287+02.0		121.7	28.0	568.0	70.0
STAGE II TOTALS	55.0	381.0	76.0	1546.0	190.0
TOTAL =	193.0	713.0	76.0	1546.0	190.0

SEEDING SCHEDULE

STATION TO STATION	SEEDING, CLASS 2 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	NITROGEN FERTILIZER NURTIENT POUND	PHOSPHORUS FERTILIZER NURTIENT POUND	POTASSIUM FERTILIZER NURTIENT POUND	MULCH, METHOD 2 ACRE	AGRICULTURAL GROUND LIMESTONE TON
STAGE I							
280+00.0 TO 280+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
280+50.0 TO 281+00.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
281+00.0 TO 281+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
281+50.0 TO 282+00.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
282+00.0 TO 282+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
282+50.0 TO 282+84.2	0.01	1.00	0.90	0.90	0.90	0.01	0.02
282+84.2 TO 282+94.8	0.01	1.00	0.90	0.90	0.90	0.01	0.02
282+94.8 TO 283+34.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00
283+34.2 TO 283+43.5	0.01	1.00	0.90	0.90	0.90	0.01	0.02
283+43.5 TO 283+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
283+50.0 TO 284+00.0	0.03	3.00	2.70	2.70	2.70	0.03	0.06
284+00.0 TO 284+50.0	0.03	3.00	2.70	2.70	2.70	0.03	0.06
284+50.0 TO 285+00.0	0.02	2.00	1.80	1.80	1.80	0.02	0.04
285+00.0 TO 285+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
STAGE II							
280+00.0 TO 280+50.0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
280+50.0 TO 281+00.0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
281+00.0 TO 281+50.0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
281+50.0 TO 282+00.0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
282+00.0 TO 282+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
282+50.0 TO 282+84.2	0.01	1.00	0.90	0.90	0.90	0.01	0.02
282+84.2 TO 282+94.8	0.01	1.00	0.90	0.90	0.90	0.01	0.02
282+94.8 TO 283+34.2	0.00	0.00	0.00	0.00	0.00	0.00	0.00
283+34.2 TO 283+43.5	0.01	1.00	0.90	0.90	0.90	0.01	0.02
283+43.5 TO 283+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
283+50.0 TO 284+00.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
284+00.0 TO 284+50.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
284+50.0 TO 285+00.0	0.01	1.00	0.90	0.90	0.90	0.01	0.02
285+00.0 TO 285+50.0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL =	0.30	26.00	23.00	23.00	23.00	0.30	0.50

EARTHWORK SCHEDULE

STATION TO STATION	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	EARTH FILL CU YD	EARTHWORK BALANCE, WASTE (+) OR SHORTAGE (-) CU YD
STAGE I				
280+00.00 TO 280+50.00	1.1	0.8	3.4	-2.5
280+50.00 TO 281+00.00	2.1	1.6	7.4	-5.9
281+00.00 TO 281+50.00	2.0	1.5	8.2	-6.7
281+50.00 TO 282+00.00	2.0	1.5	7.4	-5.9
282+00.00 TO 282+50.00	4.3	3.2	5.7	-2.5
282+50.00 TO 282+84.19	5.4	4.0	2.3	1.7
282+84.19 TO 282+94.82	2.0	1.5	0.4	1.0
EAST ABUTMENT	79.3	59.5	80.5	-21.0
BRIDGE OMISSION				
WEST ABUTMENT	79.3	59.5	80.5	-21.0
283+34.16 TO 283+43.5	1.5	1.1	3.4	-2.3
283+43.47 TO 283+50.0	1.0	0.8	2.9	-2.1
283+50.00 TO 284+00.0	6.2	4.6	29.8	-25.2
284+00.00 TO 284+50.0	3.9	2.9	24.6	-21.7
284+50.00 TO 285+00.0	2.2	1.6	23.1	-21.5
285+00.00 TO 285+50.0	0.8	0.6	15.5	-14.9
STAGE II				
280+00.00 TO 280+50.0	0.0	0.0	0.0	0.0
280+50.00 TO 281+00.0	0.0	0.0	0.0	0.0
281+00.00 TO 281+50.0	0.0	0.0	0.0	0.0
281+50.00 TO 282+00.0	0.0	0.0	0.0	0.0
282+00.00 TO 282+50.0	3.9	3.0	1.9	1.1
282+50.00 TO 282+84.2	5.5	4.1	7.0	-2.8
282+84.19 TO 282+94.8	1.7	1.3	3.5	-2.2
EAST ABUTMENT	65.6	49.2	66.6	-17.4
BRIDGE OMISSION				
WEST ABUTMENT	65.6	49.2	66.6	-17.4
283+34.16 TO 283+43.5	1.5	1.1	2.4	-1.3
283+43.47 TO 283+50.0	1.0	0.8	2.9	-2.1
283+50.00 TO 284+00.0	4.8	3.6	20.1	-16.5
284+00.00 TO 284+50.0	2.3	1.7	10.3	-8.6
284+50.00 TO 285+00.0	2.8	2.1	17.0	-14.9
285+00.00 TO 285+50.0	1.3	1.0	11.4	-10.4
TOTALS =	349.0	262.0	505.0	-243.0

NUMBER OF TURNS REQUIRED IN DETECTOR LOOPS

5 X 5		6 X 6		6 X 15		6 X 30		6 X 35		6 X 40		6 X 50		LOOP SIZE
FROM	TO	FROM	TO	FROM	TO	FROM	TO	FROM	TO	FROM	TO	FROM	TO	
				0	545	0	491	0	559	0	627	0	764	2 TURNS
0	681	0	545	574	955	492	982	560	1118	628	1255	765	1527	3 TURNS
682	954	819	1145	1433	2005	983	1636	1119	1864	1256	2091	1528	2545	4 TURNS
955	1272	1146	1527	2006	2673	1637	2455	1865	2795	2092	3136	2546	3818	5 TURNS
1273	1636	1528	1964	2674	3436	2456	3436	2796	3914					6 TURNS
1637	2045	1965	2455											7 TURNS
2046	2499	2456	3000											8 TURNS
														9 TURNS
														10 TURNS

THE NUMBERS IN THE TABLE REPRESENT THE DISTANCE FROM THE CABINET TO THE DETECTOR LOOP IN FEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**QUANTITY SCHEDULES & TURN LOOP**  
 SCALE: VERT. HORIZ.  
 DATE: \_\_\_\_\_ DRAWN BY: \_\_\_\_\_ CHECKED BY: \_\_\_\_\_

PLT DATE = 10/26/2005  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#