

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
331	(12-1) RS-1	JACKSON	16	9
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 98904				

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	DESCRIPTION	PREFORMED LINE 4" SKIP DASH WHITE FOOT	THERMOPLASTIC PAVEMENT MARKING					POLYUREA PAVEMENT MARKING SPECIAL					SHORT TERM PAVEMENT MARKING		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKERS EACH	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	PAVEMENT MARKING REMOVAL SQ FT	
			LINE 4"			LETTERS AND SYMBOLS SQ FT	LINE 4"			LETTERS AND SYMBOLS SQ FT	SKIP DASH WHITE FOOT	EDGE LINE FOOT							
			SOLID WHITE FOOT	SOLID YELLOW FOOT	SKIP DASH WHITE FOOT		SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT										
WESTBOUND																			
70+00 TO 92+45		561	2245	2245										408	359	28	28	1812	
92+45 TO 99+15	STRIEGEL ROAD							1106	601	131	92	82	73						944
99+15 TO 125+80		666	2665	2665										485	426	33	33	2151	
125+80 TO 128+85	LAKE ROAD	95	614	259		18	37							55	49	10	10	413	
128+85 TO 132+97		103	412	412										75	66	5	5	332	
132+97 TO 133+00	STATION EQ																		
133+00 TO 157+65		616	2465	2465										448	394	31	31	1989	
157+65 TO 161+09	WOOD ROAD	86	603	380			37							63	55	10	10	412	
161+09 TO 168+25		179	716	716										130	115	9	9	578	
168+25 TO 170+26	SN 039-0051		201	201	50														151
170+26 TO 185+80		389	1554	1554										283	249	19	19	1254	
185+80 TO 189+18	AIRPORT ROAD	102	601	291		17	37							61	54	11	11	421	
189+18 TO 214+00		621	2482	2482										451	397	31	31	2003	
214+00 TO 217+12	COUNTRY CLUB	93	548	260		20	37							57	50	8	8	395	
217+12 TO 243+07		649	2595	2595										472	415	32	32	2094	
243+07 TO 244+70	SN 039-0050		163	163	41														122
244+70 TO 262+47		444	1777	1777															
262+47 TO 268+48	WATSON ROAD							956	636	131	76	84	37	323	284	22	22	1434	858
268+48 TO 282+61		353	1413	1413										257	226	18	18	1140	
282+61 TO 281A+93.4	STATION EQ																		
281A+93.4 TO 283A+00		27	107	107										19	17	1	1	86	
283A+00 TO 283+00	STATION EQ																		
283+00 TO 305+50		563	2250	2250										409	360	28	28	1816	
305+50 TO 308+60	SIZEMORE DRIVE	78	556	246			37							56	50	10	10	347	
308+60 TO 318+18		240	958	958										174	153	12	12	773	
318+18 TO 325+16	WILLIAMS STREET							1673	942	177	198	66	73						1335
325+16 TO 331+50		159	634	634										115	101	8	8	512	
331+50 TO 334+49	CROSS ROAD	75	490	247			37							54	48	10	10	324	
334+49 TO 338+64		104	415	415										75	66	5	5	335	
TOTALS		6200	26464	24735	91	55	219	3735	2179	439	366	232	182	4472	3935	342	342	20620	3410
				51289					6353						8407				

NOTES: TEMPORARY PAVEMENT MARKING QUANTITIES ARE CALCULATED FROM THE PERMANENT PAVEMENT MARKING QUANTITIES
TEMPORARY PAVEMENT MARKING IS CALCULATED ONLY FOR THOSE AREAS TO BE SURFACED
SHORT TERM PAVEMENT MARKING QUANTITIES ARE CALCULATED FOR TWO APPLICATIONS FOR BOTH THE PAVEMENT AND SHOULDERS
THE STRIEGEL ROAD SECTION CONTAINS A STATION EQUATION (STA 95+79.05 BK = STA 96+03.13 AH). THE QUANTITIES HAVE BEEN ADJUSTED ACCORDINGLY
EXISTING RAISED REFLECTIVE PAVEMENT MARKERS SHALL NOT BE DISTURBED IN THE AREAS THAT WILL NOT BE SURFACED

PLOT DATE = 10/4/2005
FILE NAME = c:\projects\0901005\d901005sch.m32
PLOT SCALE = 108.4337' / IN.
USER NAME = thomashf