

# SUMMARY OF QUANTITIES

SHEET 1 OF 2

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	RURAL 100% STATE 0021	RURAL 100% STATE 0040
20400800	FURNISHED EXCAVATION	CUYD	269.00	269.00	
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQFT	158.00	158.00	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	212.50	212.50	
* 63100046	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00	1.00	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	1.00	1.00	
63200310	GUARDRAIL REMOVAL	FOOT	1271.00	1271.00	
* 63400105	GUARD POSTS	EACH	10.00	10.00	
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6.00	6.00	
64301090	ATTENUATOR BASE	SQYD	306.00	306.00	
67100100	MOBILIZATION	L SUM	1.00		1.00
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	16.00		16.00
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	2.00		2.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	19.00		19.00
70100430	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	EACH	1.00		1.00
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1.00		1.00
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.00		1.00
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.00		1.00
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.00		1.00
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.00	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	6020.00		6020.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	7310.50		7310.50
72400710	RELOCATE SIGN PANEL - TYPE 1	SQFT	99.30		99.30
72400720	RELOCATE SIGN PANEL - TYPE 2	SQFT	24.00		24.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	10093.00		10093.00
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	384.00		384.00
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	86.00		86.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	374.00		374.00
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	79.00		79.00
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	112.00		112.00
73303000	OVERHEAD SIGN STRUCTURE - MONOTUBE	FOOT	252.80		252.80
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	32.50		32.50
73400100	CONCRETE FOUNDATIONS	CUYD	22.90		22.90
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	201.50		201.50

**GENERAL DESCRIPTION OF FUND CODES:**

0021 = SAFETY - TRAFFIC SIGNALS, LIGHTING, GUARDRAIL  
 0040 = SPECIAL BRIDGE - OVERHEAD SIGN STRUCTURES

\* SPECIALTY ITEM

- VARIOUS
- 0-5 OVD SIN STR REPL 2012-06

FILE NAME =	USER NAME = ceerlockjd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
est\pw_work\p\tdot\ceerlockjd\0266557\0	46179-sit-600.dgn	DRAWN -	REVISED -		SCALE: N/A	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	•	••	Various	178	3
	PLOT SCALE = 1/8" = 1' / 32"	CHECKED -	REVISED -		CONTRACT NO. 46179								
	PLOT DATE = 10/27/2011	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								