

SCHEDULE OF QUANTITIES

MCLEAN COUNTY - I-39 - INDIVIDUAL LOCATIONS

SHEET 1 OF 2

Location No.	5-14 SB			
Structure No.	5 S 057 I039 R000.50			
County / Route	MCLEAN CO. - I-39 over SB & NB lanes - 0.5 mi. North of I-55			
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations over the SB lanes only.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	481.00	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	550.00	
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	74.00	
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	52.00	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	21.50	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	0.50	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	
<p>Note: new end supports are included in the cost of OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs. Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.</p>				

Location No.	5-15 SB			
Structure No.	5 S 057 I039 R001.00			
County / Route	MCLEAN CO. - I-39 over SB & NB lanes - 1.0 mi. North of I-55			
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations over the SB lanes only.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
20400800	FURNISHED EXCAVATION	CUYD	269.00	
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	212.50	
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	1.00	
63200310	GUARDRAIL REMOVAL	FOOT	191.00	
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.00	
64301090	ATTENUATOR BASE	SQYD	102.00	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	407.00	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	518.75	
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	71.00	
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	48.00	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	27.00	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	0.50	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	5.00	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	
<p>Note: new end supports are included in the cost of OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs. Proposed fdn. depths and elev. take into account the future profile after I-39 reconstruction. No changes to fdn. depths or top elev. will be allowed. 6 day (3 days + 3 days) advanced notice with CMS for all of I-39 covered under 5-14 SB & 5-14 NB (5S057I039R000.50)</p>				

Location No.	5-14 NB			
Structure No.	5 S 057 I039 R000.50			
County / Route	MCLEAN CO. - I-39 over SB & NB lanes - 0.5 mi. North of I-55			
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations over the SB lanes only.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
63200310	GUARDRAIL REMOVAL	FOOT	65.00	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	257.25	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	0.50	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00	
<p>Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.</p>				

Location No.	5-15 NB			
Structure No.	5 S 057 I039 R001.00			
County / Route	MCLEAN CO. - I-39 over SB & NB lanes - 1.0 mi. North of I-55			
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations over the SB lanes only.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
63200310	GUARDRAIL REMOVAL	FOOT	192.00	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	275.00	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	0.50	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00	
<p>6 day (3 days + 3 days) advanced notice with CMS for all of I-39 covered under 5-14 SB & 5-14 NB (5S057I039R000.50)</p>				

• VARIOUS
 ** D-5 OVD SIN STR REPL 2012-06

FILE NAME =	USER NAME = ceer-lock_jd	DESIGNED -	REVISED -	STATE OF ILLINOIS	SCHEDULE OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ce:\pwwork\pwwork\ceer-lock_jd\026655710	46179-ahv-schedule.dgn	DRAWN -	REVISED -	DEPARTMENT OF TRANSPORTATION	MCLEAN COUNTY - I-39 - INDIVIDUAL LOCATIONS	*	**	Various	178	98
	PLOT SCALE = 40.0000' / 1" =	CHECKED -	REVISED -		SCALE: N/A					
	PLOT DATE = 10/27/2011	DATE -	REVISED -		SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.			CONTRACT NO. 46179
ILLINOIS FED. AID PROJECT										