

SCHEDULE OF QUANTITIES
MCLEAN COUNTY – I-39 – INDIVIDUAL LOCATIONS
SHEET 2 OF 2

Location No.	5-16 SBa			
Exist. Structure No.	5 S 057 I039 R001.90			
Prop. Structure No.	5 B 057 I039 R001.90			
County / Route	MCLEAN CO. - I-39 over SB & NB lanes - 1.9 mi. North of I-55			
Scope of Work	This overhead sign structure is being replaced with a SB bridge mounted sign truss on structure 057-0213 AND a SB ground mount AND a NB ground mount.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
63200310	GUARDRAIL REMOVAL	FOOT	115.00	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	293.25	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	643.75	
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	32.50	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	0.50	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00	
6 day (3 days + 3 days) advanced notice with CMS for all of I-39 covered under 5-14 SB & 5-14 NB (5S057I039R000.50)				

Location No.	5-16 NB			
Exist. Structure No.	5 S 057 I039 R001.90			
Prop. Structure No.	N/A - Ground Mount Distance Guide sign NB at Sta. 200+30			
County / Route	MCLEAN CO. - I-39 over SB & NB lanes - 1.9 mi. North of I-55			
Scope of Work	This overhead sign structure is being replaced with a SB bridge mounted sign truss on structure 057-0213 AND a SB ground mount AND a NB ground mount.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
63200310	GUARDRAIL REMOVAL	FOOT	116.00	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	133.00	
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	153.75	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1468.50	
73400100	CONCRETE FOUNDATIONS	CUYD	3.54	
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	0.50	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00	
6 day (3 days + 3 days) advanced notice with CMS for all of I-39 covered under 5-14 SB & 5-14 NB (5S057I039R000.50)				

Location No.	5-16 SBb			
Exist. Structure No.	5 S 057 I039 R001.90			
Prop. Structure No.	N/A - Ground Mount Exit 2 BUSN 51 sign SB at start of ramp taper - Sta. 197+85			
County / Route	MCLEAN CO. - I-39 over SB & NB lanes - 1.9 mi. North of I-55			
Scope of Work	This overhead sign structure is being replaced with a SB bridge mounted sign truss on structure 057-0213 AND a SB ground mount AND a NB ground mount.			
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00	
72000300	SIGN PANEL - TYPE 3	SQFT	246.00	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3097.00	
73400100	CONCRETE FOUNDATIONS	CUYD	6.27	
6 day (3 days + 3 days) advanced notice with CMS for all of I-39 covered under 5-14 SB & 5-14 NB (5S057I039R000.50)				

- VARIOUS
- D-5 OVD SIN STR REPL 2012-06

FILE NAME =	USER NAME = ceerlockjd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES MCLEAN COUNTY – I-39 – INDIVIDUAL LOCATIONS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\pwidot\ceerlockjd\0266557\046179-sht-schedule.dgn	PLOT SCALE = 40.0000' / in.	DRAWN -	REVISED -			•	••	Various	178	99
PLOT DATE = 10/7/2011	DATE -	CHECKED -	REVISED -			SCALE: N/A	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	CONTRACT NO. 46179
										ILLINOIS FED. AID PROJECT