

MCLEAN COUNTY – U.S. 51 BUSINESS

OVERVIEW OF PROPOSED WORK

5-19
5 C 057 U051 L007.30

- Install new Traffic Signal mast arm and signal heads
See Traffic Signal Modernization plan sheets
- Wire new Traffic Signals as far as possible while keeping the old signals operational
- Install new Breakaway Ground Mount Sign at Lt. Sta. 58+40
- Remove existing truss, signage, and signal heads
- Complete the wiring of the new Traffic Signals
- Sign truss contractor must coordinate with traffic signal sub-contractor so that removal of the old truss and operation of the new traffic signals occurs on the same day.



SN 057-0024
I-55 NB

SN 057-0025
I-55 SB

MATCHLINE STATION 50+00.00

MATCHLINE STATION 59+00.00

5-20
5 B 057 U051 R007.10

- Existing Bridge Mount Sta. = 50+20
- Remove Bridge Mounted Sign Truss attached to Str. 057-0024
 - Disconnect Electrical Service - including removal of conduit and attachment clamps along bridge beam

| | | | |
|---|------------------------|-----------------|-----------|
| FILE NAME = | USER NAME = ceerlockjd | DESIGNED - JAL | REVISED - |
| ct:\pwwork\pwwork\ceerlockjd\0266557\046179-ahtr-plan-US Bus Sl.dgn | | DRAWN - | REVISED - |
| PLOT SCALE = 60.0000' / 1" = | | CHECKED - | REVISED - |
| PLOT DATE = 10/7/2011 | | DATE - 05/02/11 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**MCLEAN COUNTY – U.S. 51 BUSINESS
OVERVIEW OF PROPOSED WORK**

SCALE: 1" = 30' SHEET NO. 4 OF 7 SHEETS STA. 50+00.00 TO STA. 59+00.00

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|---------|---------|--------------|-----------|
| * | ** | Various | 178 | 144 |
| CONTRACT NO. 46179 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |

•VARIOUS COUNTIES
**D-5 OVD SIN STR REPL 2012-06