

SUMMARY OF QUANTITIES				80% FEDERAL, 20% STATE		
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011	LANDSCAPING 0031
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60266600	VALVE BOXES TO BE ADJUSTED	EACH	2	2		
60500040	REMOVING MANHOLES	EACH	5	5		
60500050	REMOVING CATCH BASINS	EACH	1	1		
60500060	REMOVING INLETS	EACH	4	4		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	216	216		
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10		
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	816	816		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32	32		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32	32		
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	37	37		
81021340	CONDUIT PUSHED, 2 1/2" DIA., PVC	FOOT	102	102		
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	139	139		
* 81400100	HANDHOLE	EACH	1	1		
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	1	1		
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	10	10		
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1	1		
* X0322918	PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER	EACH	6	6		
* X0325003	REMOVE EXISTING VALVE AND VAULT	EACH	1	1		
* X0502600	TEMPORARY LIGHTING	L SUM	1	1		
* X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2		

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES				80% FEDERAL, 20% STATE		
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0004	BRIDGE 0011	LANDSCAPING 0031
△ X5539700	STORM SEWERS TO BE CLEANED	FOOT	216	216		
X6022830	MANHOLES, SANITARY, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
X6026054	SANITARY MANHOLES TO BE REMOVED	EACH	1	1		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
* X8163090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	419	419		
* X8190205	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	278	278		
* X8360310	LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	8	8		
* X8440120	REMOVE AND RE-ERECT EXISTING LIGHTING UNIT	EACH	1	1		
Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	353	353		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	9	9		
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	200	200		
* Z0033024	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1	1		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	67		67	
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	10	10		
X2090210	POROUS GRANULAR BACKFILL (SPECIAL)	CU YD	1680	1680		
Z0038135	THREE-SIDED PRECAST CONCRETE STRUCTURES, 20' X 10'	FOOT	48		48	
X5430110	CORRUGATED STEEL ARCH LINER	FOOT	48		48	
X0327365	RIVETED CORRUGATED STEEL PIPE	L SUM	1		1	
X0327357	CONSTRUCTION VIBRATION MONITORING	L SUM	1		1	

△NON-PARTICIPATING (100% STATE)

LONGO, INC.
CONSULTING ENGINEERS
1560 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: 630/577-9100

DESIGNED - SLV
DRAWN - SLV
CHECKED - MJY, ST
DATE - 10/14/2011

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 171 OVER MILNE CREEK

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. 60+40 TO STA. 63+68

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
577	D-T	WILL	44	4
D-91-265-06			CONTRACT NO. 60B10	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		