

SUMMARY OF QUANTITIES

90% FED.
10% STATE

| PAY ITEM NUMBER | DESCRIPTION | UNIT | URBAN TOTAL QUANTITY | 0021 SAFETY |
|-----------------|--|--------|----------------------|-------------|
| 20200600 | EXCAVATING AND GRADING EXISTING SHOULDER | UNIT | 29 | 29 |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 1,414 | 1,414 |
| 25000210 | SEEDING, CLASS 2A | ACRE | 0.26 | 0.26 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 26 | 26 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 26 | 26 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 26 | 26 |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 1,281 | 1,281 |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 222 | 222 |
| 42001300 | PROTECTIVE COAT | SQ YD | 425 | 425 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 1,127 | 1,127 |
| 48101620 | AGGREGATE SHOULDERS, TYPE B 10" | SQ YD | 1,593 | 1,593 |
| 48203021 | HOT-MIX ASPHALT SHOULDERS, 6" | SQ YD | 158 | 158 |
| 50102400 | CONCRETE REMOVAL | CU YD | 3.3 | 3.3 |
| 50104000 | BRIDGE RAIL REMOVAL | FOOT | 60 | 60 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 7.0 | 7.0 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 1,288 | 1,288 |
| 60600605 | CONCRETE CURB, TYPE B | FOOT | 315 | 315 |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 1,127 | 1,127 |
| * 63000001 | STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS | FOOT | 138 | 138 |
| * 63100070 | TRAFFIC BARRIER TERMINAL, TYPE 5 | EACH | 1 | 1 |
| * 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 21 | 21 |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 24 | 24 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 2,219 | 2,219 |
| 63301990 | REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1 | EACH | 1 | 1 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70100320 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701422 | L SUM | 1 | 1 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 1 |
| * 78200420 | GUARDRAIL MARKERS, TYPE B | EACH | 75 | 75 |
| * 78201000 | TERMINAL MARKER DIRECT APPLIED | EACH | 24 | 24 |
| X0322194 | POLYMER MODIFIED PORTLAND CEMENT MORTAR | SQ FT | 0.75 | 0.75 |
| Δ X2503100 | MOWING | UNIT | 121 | 121 |
| Z0018900 | DRILL AND GROUT DOWEL BARS | EACH | 36 | 36 |
| Z0029999 | IMPACT ATTENUATOR REMOVAL | EACH | 2 | 2 |
| 64300260 | IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 2 | 2 |
| Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 257 | 257 |

* DENOTES SPECIALTY ITEM

Δ Non-participating (100% STATE)

| | | | | | | | | | | |
|-------------|------------------------|-------------------|-----------|---|---|---------------------------|--------------------|--------|--------------|-----------|
| FILE NAME = | USER NAME = .USER. | DESIGNED - EF | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | GUARDRAIL IMPROVEMENTS - DuPAGE COUNTY SUMMARY OF QUANTITIES | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| #FILE# | | DRAWN - EF | REVISED - | | | 2010-119-GRR | DuPAGE | 17 | 3 | |
| | PLOT SCALE = 50' / IN. | CHECKED - RS | REVISED - | | | VARIOUS ROUTES | CONTRACT NO. 60M56 | | | |
| | PLOT DATE = 11/9/2011 | DATE - 11/10/2011 | REVISED - | | | ILLINOIS FED. AID PROJECT | | | | |
| | | | | SCALE: 50 | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA. | | | |