

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	90% FED. / 10% STATE		
				CONSTRUCTION CODE TYPE		
				ROADWAY 100% STATE 0004	BRIDGE SN 016-1101 100% STATE 0011	*PARKING 50% CITY 50% STATE 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	64	64		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	106	106		
20101000	TEMPORARY FENCE	FOOT	140	140		
20200100	EARTH EXCAVATION	CU YD	425	425		
20800150	TRENCH BACKFILL	CU YD	33	33		
● 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2994	2994		
● 25000210	SEEDING, CLASS 2A	ACRE	0.50	0.50		
● 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	42	42		
● 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	42	42		
● 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	42	42		
● 25100630	EROSION CONTROL BLANKET	SQ YD	2251	2251		
● 25200110	SODDING, SALT TOLERANT	SQ YD	744	744		
● 25200200	SUPPLEMENTAL WATERING	UNIT	19.0	19.0		
● 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	46	46		
● 28000400	PERIMETER EROSION BARRIER	FOOT	824	824		
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	695	602		93
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	425	332		93
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	292	285		7
40600300	AGGREGATE (PRIME COAT)	TON	7	6		1
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1	1		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	127	127		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	97	97		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	434	309		45
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	325	317		8
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1536	1536		
44000100	PAVEMENT REMOVAL	SQ YD	8.1	8.1		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	122	122		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	2754	2754		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	57	57		

● SPECIALTY ITEMS

- SPECIAL PROVISION
- GUIDE BRIDGE SPECIAL PROVISION
- BDE SPECIAL PROVISION

NOTE:
PARKING LANE: COST PARTICIPATION 50% CITY OF CHICAGO AND 50% STATE

URBAN

90% FED / 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FED / 10% STATE	
				CONSTRUCTION CODE TYPE	
				ROADWAY 100% STATE 0004	BRIDGE SN 016-1101 100% STATE 0011
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1321	1321	
44000600	SIDEWALK REMOVAL	SQ FT	2056	2056	
44004250	PAVED SHOULDER REMOVAL	SQ YD	195	195	
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	16	16	
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	25	25	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1235	1235	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	2.5		2.5
50157300	PROTECTIVE SHIELD	SQ YD	1150		1150
50200100	STRUCTURE EXCAVATION	CU YD	2055		2055
50300225	CONCRETE STRUCTURES	CU YD	191.6		191.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	638.5		638.5
50300260	BRIDGE DECK GROOVING	SQ YD	1034		1034
50300300	PROTECTIVE COAT	SQ YD	1494		1494
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	5256		5256
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	156,210		156,210
50800515	BAR SPLICERS	EACH	100		100
50901730	BRIDGE FENCE RAILING	FOOT	442		442
51200956	FURNISHING METAL SHELL PILES 12" X 0.179"	FOOT	2071		2071
51202305	DRIVING PILES	FOOT	2071		2071
51203200	TEST PILE METAL SHELLS	EACH	2		2
51500100	NAME PLATE	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	131		131
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16		16
52100520	ANCHOR BOLTS 1"	EACH	32		32
52100540	ANCHOR BOLTS 1 1/2"	EACH	16		16



9901 S. Western Ave.
Chicago, IL 60643
Ph. 773-881-4788
F: 773.239.3728

DESIGNED	TS	REVISED	-
CHECKED	TPP	REVISED	-
DRAWN	JS	REVISED	-
CHECKED	TPP	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ORIOLE AVENUE AT I-90
STRUCTURE NO. 016-1101

SUMMARY OF
QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1515.1-B	COOK	101	4
CONTRACT NO. 60M79			ILLINOIS FED. AID PROJECT	

SCALE: NONE SHEET NO. X OF X SHEETS STA. TO STA.

Rev.