

9010 FED/ST

URBAN

9010 FED/ST

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE		
				ROADWAY	BRIDGE	LIGHTING
				100% STATE 0004	100% STATE 0011	100% STATE 0021
550A0030	STORM SEWERS, CLASS A, TYPE I 8"	FOOT	70	70		
55100300	STORM SEWER REMOVAL 8"	FOOT	71	71		
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	6	6		
58700300	CONCRETE SEALER	SQ FT	1370		1370	
59000200	EPOXY CRACK INJECTION	FOOT	6		6	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	128		128	
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2		
60255500	MANHOLES TO BE ADJUSTED	EACH	6			6
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4		
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1		
60500040	REMOVING MANHOLES	EACH	1			1
60500050	REMOVING CATCH BASINS	EACH	6	6		
60500205	FILLING CATCH BASINS	EACH	2	2		
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1274.0	1274.0		
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	152	152		
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2		
66400105	CHAIN LINK FENCE, 4'	FOOT	429	429		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	665	665		
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1		
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	350	350		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3866	3866		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	625	625		
72000100	SIGN PANEL - TYPE 1	SQ FT	18.8	18.8		
72000200	SIGN PANEL - TYPE 2	SQ FT	17.5	17.5		
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	32.3	32.3		
72900200	METAL POST - TYPE B	FOOT	82	82		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	219	219		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3285	3285		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1127	1127		
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	988	988		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE		
				ROADWAY	BRIDGE	LIGHTING
				100% STATE 0004	100% STATE 0011	100% STATE 0021
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	40	40		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	145	145		
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	252	252		
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	514	514		
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	514	514		
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	25	25		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	38	38		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	28	28		
78200530	BARRIER WALL MARKERS, TYPE C	EACH	100	100		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	699	699		
80400100	ELECTRICAL SERVICE INSTALLATION	EACH	1			1
80400200	ELECTRICAL UTILITY SERVICE CONNECTION	L SUM	1			1
81028200	UNDERGROUND CONDUIT, 2" DIA., GALVANIZED STEEL	FOOT	718			718
81028210	UNDERGROUND CONDUIT, 2 1/2" DIA., GALVANIZED STEEL	FOOT	282			282
81028220	UNDERGROUND CONDUIT, 3" DIA., GALVANIZED STEEL	FOOT	650			650
81028240	UNDERGROUND CONDUIT, 4" DIA., GALVANIZED STEEL	FOOT	702			702
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	951			951
81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC COATED GALVANIZED STEEL	FOOT	1270			1270
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	427			427
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE (6"x6" x4")	EACH	16			16
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE (12"x10" x6")	EACH	8			8
81300910	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE (20"x20" x6")	EACH	2			2
81603090	UNIT DUCT, 600V, 3-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	302			302
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2992			2992
81702440	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 1/0	FOOT	460			460
81100700	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., PVC COATED, GALVANIZED STEEL	FOOT	151			151

- * SPECIAL PROVISION-
- ** GUIDE BRIDGE SPECIAL PROVISION
- *** BDE SPECIAL PROVISION

ABNA DESIGN FIRM REG. 184.002117	9901 S. Western Ave. Chicago, IL 60643 Ph. 773-881-4788 F: 773.239.3728	DESIGNED TS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ORIOLE AVENUE AT I-90 STRUCTURE NO. 016-1101	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN JS	REVISED -				90	1515J-B	COOK	101	5
		CHECKED TPP	REVISED -	SCALE: NONE SHEET NO. X OF X SHEETS		STA. TO STA.		CONTRACT NO. 60M79			
		CHECKED TPP	REVISED -	ILLINOIS FED. AID PROJECT							

Rev. Rev.