

90/10 FEB/ST

URBAN

90/10 FEB/ST

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE		
				ROADWAY	BRIDGE	LIGHTING
				100% STATE 0004	100% STATE 0011	100% STATE 0021
82108100	UNDERPASS LUMINAIRE, 55 WATT, LOW PRESSURE SODIUM VAPOR	EACH	16			16
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	4			4
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	7			7
A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	3		
A2005032	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3	3		
A2008519	TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	3		
X6020084	MANHOLE, SPECIAL	EACH	1			1
X0321519	CONDUIT SUPPORT SYSTEM	L SUM	1			1
X8780107	CONCRETE FOUNDATION (SPECIAL)	FOOT	53.1			53.1
X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	273		273	
X0326144	TACTILE DETECTABLE WARNING SURFACE	SQFT	136	136		
X0326326	CABLE IN CONDUIT, TRIPLEX, 2-1/C NO. 6 AND 1-1/C NO. 8 GROUND	FOOT	2162			2162
X8300001	LIGHT POLE, SPECIAL	EACH	5			5
X7360510	REMOVE OVERHEAD SIGN STRUCTURE LIGHTING EQUIPMENT	L SUM	1			1
X0945500	PAINT EXISTING POLE COMPLETE	EACH	4			4
X5537600	STORM SEWERS TO BE CLEANED 8"	FOOT	120	120		
X6022505	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	5	5		
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	457	457		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAY)	L SUM	1	1		
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	144	144		
X7030030	WET REFLECTIVE TEMPORARY TAPE, TYPE III - 4 INCH	FOOT	9752	9752		
X7030045	WET REFLECTIVE TEMPORARY TAPE, TYPE III - 8 INCH	FOOT	988	988		
X7030050	WET REFLECTIVE TEMPORARY TAPE, TYPE III - 12 INCH	FOOT	40	40		
X7030055	WET REFLECTIVE TEMPORARY TAPE, TYPE III - 24 INCH	FOOT	127	127		
X8950090	RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1			1

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE		
				ROADWAY	BRIDGE	LIGHTING
				100% STATE 0004	100% STATE 0011	100% STATE 0021
Z0004552	APPROACH SLAB REMOVAL	SQ YD	190		190	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	70		70	
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	4		4	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2		
Z0019307	HOLES DRILLED	EACH	33			33
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	154.2	154.2		
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	4417		4417	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	71	71		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0064800	SELECTIVE CLEARING	UNIT	8	8		

* SPECIAL PROVISION
 ** GUIDE BRIDGE SPECIAL PROVISION
 *** BDE SPECIAL PROVISION
 Δ NON - PART. (100% STATE)
 ● SPECIALTY ITEMS

ABNA
 DESIGN FIRM REG. 184.002117
 9901 S. Western Ave.
 Chicago, IL 60643
 Ph. 773-881-4788
 F: 773.239.3728

DESIGNED	TS	REVISED	-
CHECKED	TPP	REVISED	-
DRAWN	JS	REVISED	-
CHECKED	TPP	REVISED	-

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

ORIOLE AVENUE AT I-90
 STRUCTURE NO. 016-1101

SUMMARY OF
 QUANTITIES

SCALE: NONE SHEET NO. X OF X SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1515.1-B	COOK	101	6
CONTRACT NO. 60M79			ILLINOIS FED. AID PROJECT	