

TREE REMOVAL/TEMPORARY FENCE			
LOCATION	TREE REMOV	TREE REMOV	TEMPORARY FENCE
	6-15	OVER 15	
STATION TO STATION	UNIT	UNIT	FOOT
HIGGINS RD.			
47+63.78, 32.81' LT		18	
48+12.99, 32.81' LT		16	
46+71.92 TO 48+10 RT			138
ORIOLE AVE.			
6+62.80, 59.10' RT	6		
6+67.42, 60.44' RT	6		
6+77.97, 59.62' RT		16	
6+79.35, 41.77' RT		14	
6+86.26, 41.35' RT		18	
9+21.00, 38.68' LT	12		
9+22.42, 41.54' LT	12		
9+22.72, 51.47' LT	10		
9+33.63, 66.05' LT	10		
9+36.02, 49.85' LT		24	
9+39.65, 62.43' LT	8		
TOTAL	64	106	138

EARTHWORK		
LOCATION	EARTH EXCAVATION	PORUS GRAN EMB SUBGR
	CU YD	CU YD
HIGGINS ROAD(WEST LEG)		
47+04.72 TO 50+00	284.3	48.1
HIGGINS ROAD(EAST LEG)		
50+00 TO 51+64.04	111.8	22.8
ORIOLE AVE.		
9+96.85 TO 11+28.08	27.6	0
TOTAL	423.7	70.9

ST SEWER CLEANING	
LOCATION	SS CLEANED
ORIOLE AVENUE	FOOT
9+25 TO 9+76 RT	51.0
9+61 TO 10+00 LT	39.0
6+11 TO 6+25.50 RT	14.5
6+36 TO 6+51 LT	15.0
TOTALS	119.5

ROADWAY ITEMS - BITUMINOUS ITEMS

LOCATION	TOTAL AREA	PARKING LANE AREA CITY OF CHICAGO	BIT MATLS PR CT	HMA BC IL-19.0 NTO	LEV BIND MM NTO	HMA SC "D" NTO	AGG PR CT
STATION TO STATION	SQ YD		GALLON	TON	TON	TON	TON
HIGGINS RD (EAST & WEST LEG)							
46+71.92 TO 49+27.82	1161.8		87.1	284.7		97.6	1.7
46+85.67 TO 48+72.33	186.7	93.4	14	88.8		15.7	0.3
50+85.30 TO 51+54.20	310.2		23.3		17.4	16.1	0.5
ORIOLE AVE.							
5+70.34 TO 6+68.22	808.9		61.6		45.5	67.9	1.2
9+29.48 TO 10+16.45	800.6		60.9		45.0	67.3	1.2
10+16.45 TO 11+28.08	131.6		9.9		7.4	11.1	0.2
BRYN MAWR AVE.							
50+49.21 TO 51+31.23	198.9		14.9		11.1	16.7	0.3
I-90 (EB) SHOULDER	146.2		11.0	32.7		12.3	
I-90 (WB) SHOULDER	124.3		9.3	27.8		10.4	
TOTAL IDOT	3775.8		285.0	389.6	126.4	317.2	5.3
TOTAL CITY OF CHICAGO		93.4	7.0	44.4		7.9	0.1
TOTAL	3869.2		292.0	434.0	126.4	325.1	5.4

TEMPORARY CONCRETE BARRIER AND IMPACT ATTENUATORS

LOCATION	TEMP CONC BARRIER	IMP ATT TEMP NRD TL3
	FOOT	EACH
I-90 KENNEDY EXPWY		
NORTH SIDE	312.5	1
SOUTH SIDE	312.5	1
TOTALS	625	2

DRAINAGE - STRUCTURES

LOCATION	NUMBER STRUCTURE	CB TA 4D T1 FOL (CHGO)	CB ADJ NEW T1 FOL	MAN ADJ NEW T1 FCL	REM CATCH BAS	DRAINAGE STR CLEAN	INLETS ADJUST	FILL CATCH BAS
STATION		EACH	EACH	EACH	EACH	EACH	EACH	EACH
ORIOLE AVE								
50+70.19, 20.32 LT	1	1						
50+70.19, 21.02' RT	2	1						
6+57.68, 22.94' LT	3	1						
49+39.95, 21.26' RT	4	1						
5+94.29				1				
6+35.30, 41.01' LT							1	
6+44.49, 0.98' LT				1				
6+46.79, 52.49' RT					1			
6+67.78, 26.90' RT					1			
6+75.00, 20.67' LT					1			
9+24.02, 21.00' RT			1					
9+34.51, 27.56' LT					1			
9+54.20, 63.98' LT					1			
10+61.81, 21.65' LT			1					
9+87.01, 2.62' RT				1				
10+55.91, 18.04' RT						1		
HIGGINS ROAD								
47+70.22, 29.23' LT	5	1						
48+08.73, 23.95' LT				1				
48+25.13, 12.14' LT								1
48+25.13, 19.69' LT								1
50+69.23, 20.01' RT					1			
TOTALS		5	2	4	6	1	1	2



9901 S. Western Ave.
Chicago, IL 60643
Ph. 773-881-4788
F: 773.239.3728

DESIGNED	TS	REVISED	-
CHECKED	TPP	REVISED	-
DRAWN	JS	REVISED	-
CHECKED	TPP	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ORIOLE AVENUE AT I-90
STRUCTURE NO. 016-1101

ORIOLE AVE, OVER KENNEDY EXPWY
SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. X OF X SHEETS

STA. TO STA.

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1515.1-B	COOK	101	9
CONTRACT NO. 60M79			ILLINOIS FED. AID PROJECT	