

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE 0005						URBAN SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE 0005					
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES						CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	663	663					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	56180	56180				
20400800	FURNISHED EXCAVATION	CU YD	780	780					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1021	1021				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	1378	1378					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	270	270				
25000210	SEEDING, CLASS 2A	ACRE	0.27	0.27					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	270	270				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	24	24					* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	188	188				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	24	24					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	210.10	210.10				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	24	24					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	49,498	49,498				
25100630	EROSION CONTROL BLANKET	SO YD	1378	1378					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	345	345				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	69	69					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	270	270				
40600300	AGGREGATE (PRIME COAT)	TON	345	345					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	611	611				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	129	129					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	188	188				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3296	3296					78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1158	1158				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	13	13				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	241	241					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1020	1020				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7455	7455					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	302	302				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	86164	86164					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	1564	1564					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	255	255					* 78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	SQ FT	108.9	108.9				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	66	66					* 78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	6682	6682				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	286	286					* 78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	676	676				
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	195	195					* 78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	541	541				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1344	1344													
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	13	13													
63200310	GUARDRAIL REMOVAL	FOOT	650	650													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5													
67100100	MOBILIZATION	L SUM	1	1													
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1													
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	115857	115857													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	319	319													

\* SPECIALTY