

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTAL	0014 BRIDGE REPAIR 90% FED. 10% STATE	0021 UNDERPASS LIGHTING 90% FED. 10% STATE
20200100	EARTH EXCAVATION	CU YD	100	100	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	282	282	
20400800	FURNISHED EXCAVATION	CU YD	488	488	
20800150	TRENCH BACKFILL	CU YD	16	16	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,805	2,805	
21400100	GRADING AND SHAPING DITCHES	FOOT	310	310	
25000210	SEEDING, CLASS 2A	ACRE	0.65	0.65	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	59	59	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	59	59	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	3,150	3,150	
28000400	PERIMETER EROSION BARRIER	FOOT	1,980	1,980	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	602	602	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	171	171	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	82	82	
40600300	AGGREGATE (PRIME COAT)	TON	1.6	1.6	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	43	43	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	10	10	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	70	70	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	56	56	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	629	629	
44000100	PAVEMENT REMOVAL	SQ YD	210	210	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	220	220	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	275	275	
50102400	CONCRETE REMOVAL	CU YD	25.6	25.6	
50104650	SLOPE WALL REMOVAL	SQ YD	516	516	
50104701	REMOVAL OF EXISTING CONCRETE DECK NO. 1	EACH	1	1	
50157300	PROTECTIVE SHIELD	SQ YD	816	816	
50200100	STRUCTURE EXCAVATION	CU YD	225	225	
50300225	CONCRETE STRUCTURES	CU YD	29.8	29.8	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	517	517	
50300280	BRIDGE DECK GROOVING	SQ YD	1,058	1,058	
50300300	PROTECTIVE COAT	SQ YD	1,326	1,326	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2,560	2,560	
50500505	STUD SHEAR CONNECTORS	EACH	5152	5152	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	117,760	117,760	
50800515	BAR SPLICERS	EACH	92	92	
51100100	SLOPE WALL 4 INCH	SQ YD	530	530	
51500100	NAME PLATES	EACH	1	1	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16	16	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	16	16	

* SPECIALTY ITEM

DATE	
BY	
FINAL SURVEY	
NOTE BOOK	
NO.	
SURVEYED	
TEMPLATE	
AREAS CHECKED	

DATE	
BY	
ORIGINAL SURVEY	
NOTE BOOK	
NO.	
SURVEYED	
TEMPLATE	
AREAS CHECKED	

FILE NAME = D:\62017-10\01.dgn
 PLOT DATE = 11/17/2011
 PLOT SCALE = 50.0000' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED	- S.J.P./K.R.K.	REVISED	-
DRAWN	- B.K.	REVISED	-
CHECKED	-	REVISED	-
DATE	- OCTOBER, 2011	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
CENTRAL AVENUE OVER I-80

SCALE: NONE SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	1415-803HB-R	COOK	51	3
			CONTRACT NO. 60P17	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.