



BILL OF MATERIALS

BAR	NO.	SIZE	LENGTH	SHAPE	
a(E)	8	#5	33'-9"	—	
h(E)	8	#6	33'-9"	—	
c(E)	37	#5	8'-9"	—	
c1(E)	16	#5	2'-5"	┘	
b(E)	9	#5	14'-8"	—	
b1(E)	9	#5	5'-2"	—	
REINFORCEMENT BARS (EPOXY COATED)				POUND	940
CONCRETE REMOVAL				CU.YD.	20.7
CONCRETE SUPERSTRUCTURE				CU.YD.	20.7
BAR SPLICERS				EACH	8
PROTECTIVE COAT				SQ. YD.	2001

LEGEND:
 HATCHED AREA INDICATES CONCRETE REMOVAL

PROPOSED SHALLOW STRIP SEAL EXPANSION JOINT (SEE SHEET 6 OF 6 FOR DETAILS)