

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	300	300					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	1584	1584					70300100	SHORT TERM PAVEMENT MARKING	FOOT	6885	6885					
21400100	GRADING AND SHAPING DITCHES	FOOT	800	800					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37025	37025					
25000210	SEEDING, CLASS 2A	ACRE	0.28	0.28					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	765	765					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	26	26					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37025	37025					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	26	26					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	255	255					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	26	26					78200420	GUARDRAIL MARKERS, TYPE B	EACH	5	5					
25100630	EROSION CONTROL BLANKET	SO YD	1334	1334					78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
25200110	SODDING, SALT TOLERANT	SO YD	250	250					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	255	255					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	36					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	155	155					
40600300	AGGREGATE (PRIME COAT)	TON	180	180					X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	200	200					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	67	67					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1500	1500					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1838	1838					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	125	125														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3745	3745														
42001300	PROTECTIVE COAT	SO YD	516	516														
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	44554	44554														
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	56	56														
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	440	440														
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	360	360														
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	474	474														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	388	388														
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2.75	2.75														
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	275	275														
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2														
63200310	GUARDRAIL REMOVAL	FOOT	350	350														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														