

INDEX OF SHEETS

- 1 TITLE SHEET
- 2 INDEX OF SHEETS, GENERAL NOTES AND HIGHWAY STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 IL ROUTE 171 OVERALL SITE PLAN
- 5-8 IL ROUTE 171 MAINTENANCE OF TRAFFIC STAGE I
- 9-12 IL ROUTE 171 MAINTENANCE OF TRAFFIC STAGE II
- 13, 13A, 13B IL ROUTE 171 MAINTENANCE OF TRAFFIC SUBSTAGE I, IA, IB, AND IC. TEMPORARY DETOUR PLAN
- 14 IL ROUTE 171 EROSION RESTORATION PLAN
- 15 S-1 DECK SLAB REPAIRS SN 016-1000 & SN 016-1001
- 16 S-2 DECK SLAB REPAIRS SN 016-1005 & SN 016-1006
- 17 S-3 DECK SLAB REPAIRS SN 016-2454 & SN 016-2455
- 18 S-4 DECK SLAB REPAIRS SN 016-2456 & SN 016-2457
- 19 S-5 DECK SLAB REPAIRS SN 016-0483 & SN 016-0485
- 20 S-6 DECK SLAB REPAIRS SN 016-0484 & SN 016-0485
- 21 S-7 DECK SLAB REPAIRS - I SN 016-0486 & SN 016-0487
- 22 S-8 DECK SLAB REPAIRS - II SN 016-0486 & SN 016-0487
- 23 S-9 DECK SLAB REPAIRS SN 016-0488 & SN 016-0489
- 24 S-10 DECK SLAB REPAIRS SN 016-1026
- 25 S-11 DECK SLAB REPAIRS SN 016-0046
- 26 S-12 DECK SLAB REPAIRS SN 016-2408
- 27 S-13 TYPICAL CROSS-SECTION-STAGE CONSTRUCTION
- 28 ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)
- * 28A-28B MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS (TC-12)
- 29 DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)
- 30 TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)
- 31 TYPICAL MARKING FOR CLOSING STATE HIGHWAYS (TC-21)
- 32 ARTERIAL ROAD INFORMATION SIGN (TC-22)

* 28C. TRAFFIC CONTROL DETAILS (TC-09)

INDEX OF HIGHWAY STANDARDS

STANDARD NO.	DESCRIPTION
280001-06	TEMPORARY EROSION CONTROL SYSTEMS
630001-10	STEEL PLATE BEAM GUARDRAIL
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-06	LANE CLOSURE, FREEWAY/EXPRESSWAY
701411-08	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP FOR SPEEDS > 45 MPH
701421-04	LANE CLOSURE, MULTILANE, DAY OPERATIONS, FOR SPEEDS > 45 MPH TO 55 MPH
701422-04	LANE CLOSURE, MULTILANE, FOR SPEEDS > 45 MPH TO 55 MPH
701606-08	URBAN LANE CLOSURE MULTILANE, 2W, WITH MOUNTABLE MEDIAN
701901-02	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
780001-03	TYPICAL PAVEMENT MARKINGS
635011-02	
701446-03	

GENERAL NOTES

1. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM IDOT BRIDGE INSPECTORS.
2. 10 FT (3 M) TRANSITIONS SHALL BE USED TO MATCH PROPOSED ITEMS OF WORK TO EXISTING ITEMS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEM OF WORK SPECIFIED.
3. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 AT LEAST 72 HOURS PRIOR TO THE START OF WORK.
4. THE RESIDENT ENGINEER SHALL CONTACT THE AREA TRAFFIC FIELD ENGINEER, PATRICE HARRIS, AT (708) 597-9800 AT LEAST TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
5. ALL PAVEMENT MARKINGS AND RAISED REFLECTORS AFFECTED BY THE BRIDGE REPAIRS SHALL BE REPLACED. NOMINAL QUANTITIES HAVE BEEN INCLUDED IN THE CONTRACT FOR THIS WORK.
6. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
7. DO NOT SCALE THESE PLANS FOR CONSTRUCTION PURPOSES. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.
8. DURING CONSTRUCTION OPERATIONS, LOOSE MATERIAL DEPOSITS THAT OBSTRUCT THE FLOW OF WATER IN DRAINING THE AREA SHALL BE REMOVED BEFORE THE END OF EACH WORK DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES (NEW AND EXISTING) SHALL BE FREE FROM ALL DIRT AND DEBRIS. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE ITEM FOR DECK SLAB REPAIR.
9. BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES, SYMBOLS AND LETTERS (AND RAISED REFLECTIVE MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS AND RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE AS DIRECTED BY THE ENGINEER.
10. THE PLANS DO NOT REPRESENT A COMPLETE DEPICTION OF ALL UTILITIES THAT MAY BE IMPACTED BY THE PROPOSED WORK. THE CONTRACTOR SHALL CONDUCT HIS OR HER OWN INVESTIGATION TO DETERMINE THE OWNERSHIP OF IMPACTED UTILITIES. THE CONTRACTOR SHALL COORDINATE WITH THE UTILITY OWNERS AND MAY BE REQUIRED TO PROVIDE TEMPORARY SUPPORT, ADJUST, RELOCATE OR REMOVE UTILITIES THAT ARE IMPACTED BY THE PROPOSED IMPROVEMENT. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
11. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHTTIME OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTED ADVERSE VISIBILITY TO THE MOTORING PUBLIC.
12. THERE IS NO REPAIR WORK NEEDED FOR SN 016-0987 AND SN 016-0483

FILE NAME =	USER NAME = rgo11	DESIGNED - EM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 171 INDEX OF SHEETS, GENERAL NOTES, & HIGHWAY STANDARDS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - DR	REVISED -			373	2011-077-BR	COOK	32	2	
	PLOT SCALE = 1/8" = 1'-0"	CHECKED - JMH	REVISED -			CONTRACT NO. 60R03					
	PLOT DATE = 11/14/2011	DATE - AUGUST, 2011	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE: SHEET NO. OF SHEETS STA. TO STA.							

Rev.