				1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
				CONSTRUCTION TYPE CODE																	
			URBAN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN
			TOTAL	016-1000	016-1001	016-1005	016-1006	016-2454	016-2455	016-2456	016-2457	016-0985	016-0484	016-0485	016-0486	016-0487	016-0488	016-0489	016-1026	016-0046	016-2408
				0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014	0014
CODE NO.	ITEM	UNIT	QUANTITY 100% STATE	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
20200100	EARTH EXCAVATION	CU YD	8											8							
28000305	TEMPORARY DITCH CHECKS	FOOT	20											20							
28100105	STONE RIPRAP, CLASS A3	SQ YD	9											9							
28200200	FILTER FABRIC	SQ YD	16											16							
50157300	PROTECTIVE SHIELD	SQ YD	3822	386	386	388	388								793	635	305			436	105
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	15											15							
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	6	0.34	0.34	0.34	0.34	0.34	0.34	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33
67100100	MOBILIZATION	L SUM	1	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.05	0.05	0.05	0.05	0.05	0.05	0.05	0.05
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	1.6	1.6	1.6	1.6	1.6	1.6	1.7	1.7	1.7	1.7	1.7	1.7	1.7	1.7	1.7	1.7	1.7	1.7
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15400	1100	1100	1100	1100	1100	1100		1100	1100	1100	1100	1100	1100	1100	1100			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	66											66							
• 78008210	POLYUREA PAVEMENT MARKING, TYPE I - LINE 4"	FOOT	1998	111	111	111	111	111	111	111	111	111	111	111	111	111	111	111	111	111	111
• 78008240	POLYUREA PAVEMENT MARKING, TYPE I - LINE 8"	FOOT	9352	668	668	668	668	668	668		668	668	668	668	668	668	668	668			
* 78008250	POLYUREA PAVEMENT MARKING, TYPE I - LINE 12"	FOOT	810	45	45	45	45	45	45	45	45	45	45	45	45	45	45	45	45	45	45
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EA	78	4	4	4	4	4	4	4	4	4	4	4	4	5	5	5	5	5	5
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EA	112	8	8	8	8	8	8		8	8	8	8	8	8	8	8			
* 78100300	REPLACEMENT REFLECTOR	EA	168	24		10		10	10	10	10	10	10	10	10	10	10	34			
78200530	BARRIER WALL MARKERS, TYPE C	EACH	10											10							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2178	121	121	121	121	121	121	121	121	121	121	121	121	121	121	121	121	121	121
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	112	8	8	8	8	8	8		8	8	8	8	8	8	8	8			
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.08	0.08	0.07	0.07	0.07	0.07		0.07	0.07	0.07	0.07	0.07	0.07	0.07	0.07			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1							0.25									0.25	0.25	0.25
X7030030	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	41916	2994	2994	2994	2994	2994	2994		2994	2994	2994	2994	2994	2994	2994	2994			
X7030045	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	9352	668	668	668	668	668	668		668	668	668	668	668	668	668	668			
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	61.6						8.6	3.0	14.8			12.2	3.6	7.0	2.0	3.8		6.6	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	1511.1	5.0	9.4	1.0	1.0	197.0	265.0	191.0	287.0	91.0	80.0	93.0	110.0	83.0	28.0	51.0	1.0	17.0	0.7
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1		1																
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1											1							
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	77	5.5	5.5	5.5	5.5	5.5	5.5		5.5	5.5	5.5	5.5	5.5	5.5	5.5	5.5			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			0.13	0.13	0.13	0.13						0.12	0.12	0.12	0.12			
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMINGS	EACH	5							2									1	1	1

• - INDICATES SPECIALTY ITEM

Rev.

FILE NAME =	USER NAME = $USER$	DESIGNED - EM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 171 SUMMARY OF QUANTITIES	F.A.P. RTE. 373	SECTION 2011-077-BR
		DRAWN - DR	REVISED -			COUNTY COOK	TOTAL SHEETS 32 / SHEET NO. 3
	PLOT SCALE = $SCALE$	CHECKED - JMH	REVISED -			CONTRACT NO. 60R03	
	PLOT DATE = $DATE$	DATE - AUGUST, 2011	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT	

$FILEL$