10/31/2011 3:40:55 PM
P:\P40567\P40567\CIVIL\SHT\GENERAL\SHT\101QUA01_INTERIM.SHT

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	1 ROADWAY 0003 KANE	2 ROADWAY 0003 DUPAGE	3 DUPAGE CONTE	4 0005 KANE	5 KANE FOXFIELD COMMONS	6 KANE KIRK ROAD	7 KANE CHARLESTOWNE MALL WEST	8 KANE 38TH AVENUE	9 DUPAGE COUNTY CONSTRUCTION FUNDING CODE TRAFFIC SIGNALS 0021 SMITH / KAUTZ ROAD	10 PHEASANT RUN	11 POWIS ROAD	12 ATLANTIC DRIVE	13 IL ROUTE 59	14 100% ST. CHARLES EVP	15 20% W.C. FPD EVP	16 KANE DUPAGE INTERCONNECT 0021 KANE NHS	17 KANE NHS	18 DUPAGE NHS	19 LIGHTING 0021 KANE	20 LIGHTING 0021 DUPAGE	21 DUPAGE CO. 0010 BRIDGE	22 DUPAGE CO. 0040 RETAINING WALL	23 KANE CO. KANE CO. 0043 100% CITY OF ST. CHARLES	24 62410 80% FED. 0021 20% ST. CHARLES SW
				80% FED. 20% STATE		100% PRIVATE ENTITY	80% FED. 20% STATE	100% ST. CHARLES	80% FED. 10% STATE 10% KANE COUNTY	100% ST. CHARLES		80% FED. 10% STATE 10% ST. CHARLES	100% ST. CHARLES	80% FED. 10% STATE 5% DuPage 5% W. CHICAGO	100% ST. CHARLES	80% FED. 20% STATE			KANE DUPAGE	80% FED. / 20% STATE								
20101100	TREE TRUNK PROTECTION	EACH	40		40																							
20100500	TREE REMOVAL, ACRES	ACRE	0.3		0.3																							
20200100	EARTH EXCAVATION	CU YD	53,183		53,183																							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	21,590	367	21,223																							
20400800	FURNISHED EXCAVATION	CU YD	61,103		61,103																							
20800150	TRENCH BACKFILL	CU YD	5231	986	4211																					34		
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	71,384	2,185	69,145		54																					
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	27,392	1,216	26,176																							
* 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	36,581		36,581																							
* 25000210	SEEDING, CLASS 2A	ACRE	18.8	0.3	18.5																							
* 25000310	SEEDING, CLASS 4	ACRE	7.5		7.5																							
* 25000314	SEEDING, CLASS 4B	ACRE	2.2		2.2																							
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2,745	57	2,688																							
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2,745	57	2,688																							
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2,745	57	2,688																							
* △ 25000775	SELECTIVE MOWING STAKES	EACH	15		15																							
* 25100115	MULCH, METHOD 2	ACRE	28.5	1.4	27.1																							
* 25100630	EROSION CONTROL BLANKET	SQ YD	135,303	3,401	131,902																							
* 25200110	SODDING, SALT TOLERANT	SQ YD	29,838	2,185	27,599		54																					
* 25200200	SUPPLEMENTAL WATERING	UNIT	298.2	21.9	276.3																							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	16,907	843	16,064																							
28000305	TEMPORARY DITCH CHECKS	FOOT	790		790																							
28000400	PERIMETER EROSION BARRIER	FOOT	30,761	2,936	27,825																							
28000500	INLET AND PIPE PROTECTION	EACH	170		170																							
28000510	INLET FILTERS	EACH	249	28	221																							
28100107	STONE RIPRAP, CLASS A4	SQ YD	113		113																							
28200200	FILTER FABRIC	SQ YD	113		113																							
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	7,740	278	7,462																							
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	192,674		192,674																							
35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	2,339		2,339																							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24,409	1,063	19,918		3,428																					
40600300	AGGREGATE (PRIME COAT)	TON	453.1	11.4	303.7		138.0																					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52.0				52.0																					
~~40600635~~	~~LEVELING BINDER (MACHINE METHOD), N70~~	~~TON~~	~~200.0~~				~~200.0~~																					
X4421000	PARTIAL DEPTH PATCHING	TON	200				200																					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,749.6	445.6			1,304.0																					
40600895	CONSTRUCTING TEXT STRIP	EACH	2				2																					

△ NON-PARTICIPATING

* DENOTES SPECIALTY ITEM

AECOM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011
DRAWN BY: AFC
CHECKED BY: NJH

SOQ-01
Rev.