F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
				URBAN		80% FED. 20% STATE		100% PRIVATE ENTITY	80% FED. 20% STATE		100% ST. CHARLES	80% FED. 10% ST. 10% KANE	KANE COUNTY 100% ST. CHARLES		80% FED. 10% STATE 10% ST. CHARLES		100% ST. CHARLES	80% FED. 10% STATE 5% DUPAGE 5% W.C.		100% ST. CHARLES	80% FED. 20% STATE			80% FED./20% STATE		DUPAGE CO. 80% FED/20% ST.		KANE	62410 KANE
				CONSTRUCTION FUNDING CODE																							
				ROADWAY					TRAFFIC SIGNALS											KANE	DUPAGE	INTERCONNECT			LIGHTING				80% FED
				0003			0005		0021													0021			0021	0010	0040	0043	0021
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	KANE	DUPAGE	DUPAGE CONTE	KANE	KANE FOXFIELD COMMONS	KANE KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH / KAUTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	100% W.C. FPD EVP	KANE NHS	KANE NHS	DUPAGE NHS	KANE	DUPAGE	BRIDGE	RETAINING WALL	100% CITY OF ST. CHARLES	20% ST. CHARLES SW
50300280	CONCRETE ENCASEMENT	CU YD	173.5																					173.5			
50300300	PROTECTIVE COAT	SQ YD	8,024																					5,225	2,799		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1																					1			
50500505	STUD SHEAR CONNECTORS	EACH	21,996																					21,996			
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1																					1			
50800105	REINFORCEMENT BARS	POUND	1,244		1,244																						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	752,420																					559,490	192,930		
50800515	BAR SPLICERS	EACH	2676																					2676			
51201800	FURNISHING STEEL PILES HP14X73	FOOT	16,932																					16,932			
51202305	DRIVING PILES	FOOT	16,932																					16,932			
51203800	TEST PILE STEEL HP14X73	EACH	5																					5			
51204650	PILE SHOES	EACH	328																					328			
51500100	NAME PLATES	EACH	1																					1			
52000020	PREFORMED JOINT SEAL 1 3/4"	FOOT	300																					300			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	299																					299			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	52																					52			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	52																					52			
52100520	ANCHOR BOLTS, 1"	EACH	104																					104			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	104																					104			
52100540	ANCHOR BOLTS, 1 1/2"	EACH	52																					52			
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	6		6																						
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	4		4																						
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2		2																						
54010302	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	573		573																						
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	318		318																						
54010704	PRECAST CONCRETE BOX CULVERT 7' X 4'	FOOT	174		174																						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	94		94																						
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3		3																						
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	7		7																						
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2		2																						
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6		6																						
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	2		2																						

* DENOTES SPECIALTY ITEM

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
CHECKED BY: NJH

SOQ-03
Rev.