

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE, KANE	647	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

80% FED. 20% STATE  
 100% PRIVATE ENTIT.  
 85% FED. 15% STATE  
 100% ST. CHARLES  
 100% ST. CHARLES  
 80% FED. 10% STATE 10% ST. CHARLES  
 100% ST. CHARLES  
 80% FED. 10% STATE 10% ST. CHARLES  
 100% ST. CHARLES  
 80% FED. 20% STATE  
 URBAN  
 KANE COUNTY 100% ST. CHARLES  
 DUPAGE COUNTY  
 80% FED./20% STATE  
 DUPAGE Co.  
 KANE Co. 62410

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION FUNDING CODE																					
				ROADWAY				TRAFFIC SIGNALS																LIGHTING	
				0003		0005	0021																0010	0040	
KANE	DUPAGE	DUPAGE CONTE	KANE	FOXFIELD COMMONS	KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH / KALTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	100% W.C. FFD	KANE NHS	KANE NHS	DUPAGE NHS	KANE	DUPAGE	BRIDGE	RETAINING WALL	0043	0021		
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	4,984																						
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	3,002																						
* 81028410	UNDERGROUND CONDUIT, PVC, 6" DIA.	FOOT	7																						
* 81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	407																						
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA. PVC	FOOT	3,386																						
* 81400100	HANDHOLE	EACH	17																						
* 81400200	HEAVY-DUTY HANDHOLE	EACH	35																						
* 81400300	DOUBLE HANDHOLE	EACH	10																						
* 81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	36,257																						
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	800																						
* 81702220	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C 350MCM	FOOT	645																						
* 81800290	AERIAL CABLE 3-1/C NO. 1/0 WITH MESSENGER WIRE	FOOT	70																						
* 81800300	AERIAL CABLE 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4,745																						
* 82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	30																						
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	149																						
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	10																						
* 82200700	AVIATION OBSTRUCTION WARNING LUMINAIRE	EACH	8																						
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	134																						
* 83060450	LIGHT POLE, GALVANIZED STEEL, 45 FT. M.H., 15 FT. MAST ARM	EACH	14																						
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	2,041																						
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	157																						
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	24																						
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	34																						
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	34																						
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3																						
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2																						
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2																						
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	6																						
* 85000400	MAINTENANCE OF TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1																						
* 86400100	TRANSCIEVER - FIBER OPTIC	EACH	7																						
* 87001275	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (XLP-TYPE TC) 3/C NO.4 AND NO. 6 GROUND	FOOT	2,950																						
* 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 82.5/125, MM12F SM12F	FOOT	18,492																						
* 87200400	SPAN WIRE	FOOT	779																						
* 87200500	TETHER WIRE	FOOT	779																						
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	18,463																						

\* DENOTES SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE  
 HORIZ: NONE  
 DATE: NOVEMBER 1, 2011

DRAWN BY: AFC  
 CHECKED BY: NJH

S00-08  
 Rev.