

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE, KANE	647	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

URBAN KANE COUNTY CONSTRUCTION FUNDING CODE 80% FED./20% STATE DuPAGE CO. KANE CO. 62410

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION FUNDING CODE																					
				ROADWAY				TRAFFIC SIGNALS																LIGHTING	
				0003		0005	0021																0021	0010	
KANE	DUPAGE	DuPAGE CONTE	KANE	FOXFIELD COMMONS	KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH/KALTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	100% W.C. FPD EVP	KANE NHS	KANE NHS	DUPAGE NHS	KANE	DUPAGE	BRIDGE	RETAINING WALL	0043 CITY OF ST. CHARLES	0021 20% ST. CHARLES SW		
* 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6					2	1																
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	6					3	1	1															
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	16					2	2	2	4	4	2												
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4					2	2																
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	97					8	10	10	13	22	18												
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	75					9	10	12	11	14	10												
* 88600100	DETECTOR LOOP, TYPE I	FOOT	4,693					1,248	789	1,763	701	192													
* 88600700	PREFORMED DETECTOR LOOP	FOOT	6,226								329	1,516	1,516	1,980	885										
* 88700200	LIGHT DETECTOR	EACH	20										5		12	3									
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	5										1		3	1									
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	18					6		2	4	4	2												
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	4								1	1	1												
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1																						
* 89502300	REMOVE ELECTRICAL CABLE FROM CONDUIT	FOOT	25,906								8,208		8,379	8,339	980										
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	8					1	1	1	1	1	1	1	1										
* 89502380	REMOVE EXISTING HANDHOLE	EACH	53								11		9	11				4	18						
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	28								10		9	9											
* 89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1										1												
X0301797	GATE REMOVAL	EACH	2			2																			
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	116			116																			
* X0322932	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL (WETLAND)	GALLON	2.5			2.5																			
X0322992	COARSE SAND PLACEMENT, 4"	SQ YD	111			111																			
* X0323003	TEMPORARY ELECTRIC SERVICE INSTALLATION	EACH	1																		1				
X0323149	TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	8,060																				8,060		
* X0324907	TEMPORARY MAST ARM, 15 FT.	EACH	4																4						
* X0325134	WIRELESS INTERCONNECT (COMPLETE)	EACH	1										1												
X0325225	BRICK PAVEMENT REMOVAL AND REPLACEMENT	SQ FT	222			222																			
* X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1																1						
* X0326148	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	23																14	9					
* X0326884	TRAFFIC SIGNAL WOOD POLE, 45 FT, CLASS 5	EACH	4											4											
* X0326885	VIDEO DETECTION SYSTEM	EACH	1										1												
X0327024	FIRE HYDRANTS TO BE REMOVED & SALVAGED	EACH	4																					4	
X0327139	AGGREGATE COLUMN GROUND IMPROVEMENT	L SUM	1																					1	
X0327294	STORM SEWERS TO BE GROUTED	CU YD	23			23																			
X0487700	SANITARY SEWER REMOVAL 10"	FOOT	20			20																			
X0487800	SANITARY SEWER REMOVAL 12"	FOOT	20			20																			
X0210400	STUMP REMOVAL ONLY	UNIT	95			95																			

\* DENOTES SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE  
 HORIZ: NONE  
 DATE: NOVEMBER 1, 2011

DRAWN BY: AFC  
 CHECKED BY: NJH

S0Q-10  
 Rev.