

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE, KANE	647	15A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

URBAN

KANE COUNTY

80% FED. 10% STATE
 10% ST. CHARLES
 80% FED. 10% STATE
 10% ST. CHARLES
 80% FED. 10% STATE
 10% ST. CHARLES

80% FED. / 20% STATE

DUPAGE CO. KANE CO. KANE CO. 62410

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION FUNDING CODE																							
				ROADWAY				100% ST. CHARLES				TRAFFIC SIGNALS				KANE DUPAGE				INTERCONNECT				LIGHTING			
				KANE	DUPAGE	DUPAGE CONTE	KANE	FOXFIELD COMMONS	KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH / KALTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	100% W.C. FPD EVP	KANE NHS	KANE NHS	DUPAGE NHS	KANE	DUPAGE	BRIDGE	RETAINING WALL	0043 CITY OF ST. CHARLES	0021 20% ST. CHARLES SW
X0327369	SANITARY SEWER, DUCTILE IRON, 10"	FOOT	20																								
X0327368	SANITARY SEWER, DUCTILE IRON, 12"	FOOT	20	20																							
X0327371	PLUG EXISTING PIPE	CU YD	67	51	16																						
*XX004907	GATE VALVE 12" WITH VAULT, 5' DIAMETER	EACH	5																					5			
*XX007558	GATE VALVE 6" WITH VAULT, 4' DIAMETER	EACH	1																					1			
*X8302405	LIGHT POLE, ALUMINUM, 20 FT. M.H., 6 FT. MAST ARM	EACH	16																						16		
*X8302415	LIGHT POLE, ALUMINUM, 20 FT. M.H., TWIN 6 FT. MAST ARM	EACH	7																						7		
XX006653	FENCE (SPECIAL)	FOOT	5,081		5,081																						
*81026464	CONDUIT ENCASED, REINFORCED CONCRETE, 6" DIA., PVC 3 WIDE X 4 HIGH	FOOT	210																						210		
*X8100053	CONDUIT ENCASED, 6" DIA., GALVANIZED STEEL	FOOT	12																						12		
*81304520	JUNCTION BOX EMBEDDED IN STRUCTURE 18"X8"X8"	EACH	4																						4		
*X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	3																						3		
*56103550	DUCTILE IRON WATER MAIN, CLASS 52, 12"	FOOT	2,114																						2,114		
*Z0045450	PRESSURE CONNECTION 12" WITH VAULT 5' DIAMETER	EACH	1																						1		
*X0327367	STEEL CASING PIPE, BORE & JACK 24"	FOOT	140																						140		
*X5640050	CAP EXISTING FIRE HYDRANT	EACH	4		4																						
*X8800025	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, SPAN WIRE MOUNTED	EACH	24																						24		
*87302705	ELECTRICAL CABLE AERIAL SUSPENDED, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 IC	FOOT	106																						106		
*X8000020	EMERGENCY VEHICLE PREEMPTION DETECTOR SUPPORT, PARAPET MOUNTED	EACH	1																						1		
*87702726	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS 48 FT. AND 26 FT.	EACH	1								1																
*87702742	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 50 FT. AND 22 FT.	EACH	1																						1		
*87704555	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 55 FT. AND 32 FT.	EACH	1																						1		
*87704642	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 64 FT. AND 32 FT.	EACH	1																						1		
*87704740	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 68 FT. AND 40 FT.	EACH	1																						1		
*87704844	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 70 FT. AND 44 FT.	EACH	1																						1		
*X8710012	FIBER OPTIC CABLE IN CONDUIT (INSTALL ONLY)	FOOT	1000																						1000		
	WALL MOUNTED SIGN SUPPORT FOR TYPE 4 PANEL (SPECIAL)	EACH	1																						1		
*X8620200	UNINTERRUPTIBLE POWER SUPPLY, SPECIAL	EACH	8						1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1		
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	322																						322		

* DENOTES SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE
 HORIZ: NONE
 DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
 CHECKED BY: NJH

SOQ-13