

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	34
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62410

STRUCTURE SCHEDULE OF ROADWAY CULVERTS - NORTH AVENUE

STR. NO	STATION OFFSET	PAY ITEM	N. INVERT (FT.)	W. INVERT (FT.)	S. INVERT (FT.)	E. INVERT (FT.)
S 600	3284+00, 85.4' LT	PRC FLAR END SEC 12	757.80	-	-	-
S 601	3284+00, 86.5' RT	PRCF END S EL EQRS 36	-	-	757.00	-
S 603	3314+82, 84.5' LT	BOX CUL END SEC C1*	753.51	-	-	-
S 604	3314+83, 39.0' LT	MAN TA 5 DIA T1F CL	753.29	-	753.29	-
S 605	3314+85, 90.7' RT	BOX CUL END SEC C1*	-	-	753.00	-
S 607	3340+78, 79.4' LT	BOX CUL END SEC C2*	750.98	-	-	-
S 607A	3340+82, 79.5' LT	BOX CUL END SEC C2*	750.98	-	-	-
S 608	3340+78, 79.2' RT	BOX CUL END SEC C2*	-	-	750.92	-
S 608A	3340+82, 79.3' RT	BOX CUL END SEC C2*	-	-	750.92	-
S 613	3367+00, 95.0' LT	BOX CUL END SEC C1*	756.32	-	-	-
S 614	3367+00, 123.6' RT	BOX CUL END SEC C1*	-	-	756.28	-
S 616	3377+45, 86.3' LT	BOX CUL END SEC C3*	752.80	-	-	-
S 617	3377+45, 87.3' RT	BOX CUL END SEC C3*	-	-	752.52	-
S 619	3407+60, 91.5' LT	BOX CUL END SEC C1*	767.89	-	-	-
S 620	3407+60, 92.6' RT	BOX CUL END SEC C1*	-	-	767.62	-

PIPE SCHEDULE OF ROADWAY CULVERTS - NORTH AVENUE

PIPE NO.	UP STREAM STR. NO.	UP STREAM INVERT	DOWN STREAM STR. NO.	DOWN STREAM INVERT	PIPE LENGTH (FEET)	PIPE DIA. (INCHES)	PIPE SLOPE (%)	PAY ITEM DESCRIPTION	TRENCH BACKFILL (CU YD)
P 600	S 600	757.80	S 601	757.00	156	36	0.52	SS CL A 1 EQRS 36	38.10
P 603	S 603	753.51	S 604	753.29	43	3X2	0.52	PCBC 3X2	16.20
P 604	S 604	753.29	S 605	752.64	127	3X2	0.52	PCBC 3X2	72.80
P 607	S 607	750.98	S 608	750.92	159	4X2	0.04	PCBC 4X2	21.20
P 607A	S 607A	750.98	S 608A	750.92	159	4X2	0.04	PCBC 4X2	21.20
P 613	S 613	756.32	S 614	756.28	219	3X2	0.02	PCBC 3X2	227.30
P 616	S 616	752.80	S 617	752.52	174	7X4	0.17	PCBC 7X4	100.40
P 619	S 619	767.89	S 620	767.62	184	3X2	0.15	PCBC 3X2	108.10

NOTE:

- THE STRUCTURES WITH AN ASTERISK (\*) ARE DENOTED ACCORDINGLY.  
 BOX CULVERT END SECTION CULVERT NO. 1 (BOX CUL END SEC C1) IS FOR A PRECAST CONCRETE BOX CULVERT 3'X2'  
 BOX CULVERT END SECTION CULVERT NO. 2 (BOX CUL END SEC C2) IS FOR A PRECAST CONCRETE BOX CULVERT 4'X2'  
 BOX CULVERT END SECTION CULVERT NO. 3 (BOX CUL END SEC C3) IS FOR A PRECAST CONCRETE BOX CULVERT 7'X4'



SCHD-6

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)
NAME	DATE	
		SCHEDULE OF DRAINAGE QUANTITIES

SCALE: VERT: NONE  
 HORIZ: NONE  
 DATE: NOVEMBER 1, 2011

DRAWN BY: AFC  
 CHECKED BY: EBY