

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0003				0021			0031			0021					
				ROADWAY				SHARED USE PATH			LANDSCAPING			TRAFFIC SIGNALS					
				KLASEN ROAD	VIRGINIA ROAD	INTERCONNECT													
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1203	1203															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	656	656															
20101000	TEMPORARY FENCE	FOOT	105	105															
20101700	SUPPLEMENTAL WATERING	UNIT	1	1															
20200100	EARTH EXCAVATION	CU YD	41250	41250															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2995	2995															
20400800	FURNISHED EXCAVATION	CU YD	13000	13000															
20800150	TRENCH BACKFILL	CU YD	5371	5371															
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	61251	61251															
25000210	SEEDING, CLASS 2A	ACRE	12.75	12.75															
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	880	880															
25000500	POTASSIUM FERTILIZER NUTRIENT	POUND	880	880															
25100115	MULCH, METHOD 2	ACRE	3.00	3.00															
25100630	EROSION CONTROL BLANKET	SQ YD	61251	61251															
25200110	SODDING, SALT TOLERANT	SQ YD	9529	9529															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1270	1270															
28000305	TEMPORARY DITCH CHECKS	FOOT	98	98															
28000400	PERIMETER EROSION BARRIER	FOOT	5892	5892															
28000510	INLET FILTERS	EACH	177	177															
28100107	STONE RIPRAP CLASS A4	SQ YD	8	8															
28200200	FILTER FABRIC	SQ YD	23346	23346															
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	1569	1569															
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	65331	57730				7601											
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	5	5															
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	8626	8626															
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5803	5803															
40600300	AGGREGATE (PRIME COAT)	TON	19.3	19.3															
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	762					762											
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	3195	3195															
40701951	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"	SQ YD	4923	4923															
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	1748	1748															
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	47910	47910															
42001300	PROTECTIVE COAT	SQ YD	59189	59189															
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	74	74															
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1788	1788															
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1318					1318											

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0003		0021		0031		0021									
				ROADWAY		SHARED USE PATH		LANDSCAPING		TRAFFIC SIGNALS									
				KLASEN ROAD	VIRGINIA ROAD	INTERCONNECT													
44000100	PAVEMENT REMOVAL	SQ YD	26195	26195															
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3968	3968															
44000400	GUTTER REMOVAL	FOOT	24	24															
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4088	4088															
44003100	MEDIAN REMOVAL	SQ FT	1934	1934															
44004250	PAVED SHOULDER REMOVAL	SQ YD	14418	14418															
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1059	1059															
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	757	757															
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1151	1151															
50105220	PIPE CULVERT REMOVAL	FOOT	787	787															
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	217	217															
542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	97	97															
542C0220	PIPE CULVERTS, CLASS C, TYPE 1 15"	FOOT	370	370															
542C5470	PIPE CULVERTS, CLASS C, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	241	241															
542C5491	PIPE CULVERTS, CLASS C, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	211	211															
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	15	15															
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2															
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2															
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1															
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1															
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	4	4															
54215547	METAL END SECTIONS 12"	EACH	8	8															
54215550	METAL END SECTIONS 15"	EACH	12	12															
54215760	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	4	4															
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1															
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	2198	2198															
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	753	753															
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	226	226															
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	196	196															
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	677	677															
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	112	112															
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	722	722															
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3943	3943															
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	475	475															
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1412	1412															
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	526	526															

FILE NAME = J:\2278\cad\sheet\02-SummaryOfQuantities
 USER NAME = kwh.ctr
 X2278_SQ_01.dgn
 PLOT SCALE = 1:8000 / 1"
 PLOT DATE = 12/9/2011

DESIGNED - DTE
 DRAWN - DTE
 CHECKED - GAB
 DATE - 10/24/11

REVISED - 1-11-12
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES
 SCALE: SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.U. RTE. 3887	SECTION 96-00209-01-PV	COUNTY MCHENRY	TOTAL SHEETS 271	SHEET NO. 5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT HPP-4061003				
CONTRACT NO. 63553				