

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0021	0042
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42		
20200100	EARTH EXCAVATION	CU YD	2690	2690		
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	142	142		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12771	12771		
* 25000210	SEEDING, CLASS 2A	ACRE	3	3		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	239	239		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	239	239		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	239	239		
25100630	EROSION CONTROL BLANKET	SQ YD	12771	12771		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	265	265		
28000305	TEMPORARY DITCH CHECKS	FOOT	112	112		
28000400	PERIMETER EROSION BARRIER	FOOT	2703	2703		
28000500	INLET AND PIPE PROTECTION	EACH	7	7		
28000510	INLET FILTERS	EACH	20	20		
28100107	STONE RIPRAP, CLASS A4	SQ YD	28	28		
28200200	FILTER FABRIC	SQ YD	28	28		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	701	701		
35501330	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SQ YD	2024	2024		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2766	2766		
40600300	AGGREGATE (PRIME COAT)	TON	41	41		
40600827	POLYMERIZED LEVEL BINDER (MACHINE METHOD), IL-4.75, N50	TON	521	521		
* 40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	309	309		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	109	109		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	868	868		
44000100	PAVEMENT REMOVAL	SQ YD	554	554		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	776	776		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3135	3135		
44004250	PAVED SHOULDER REMOVAL	SQ YD	32	32		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	32	32		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	37	37		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2167	2167		
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	300	300		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	40	40		
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2		
50105220	PIPE CULVERT REMOVAL	FOOT	280	280		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	116	116		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	40	40		
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	311	311		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	10	10		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
54213873	STEEL END SECTIONS 18"	EACH	2	2		
54213879	STEEL END SECTIONS 24"	EACH	8	8		

* SEE SPECIAL PROVISIONS
** DENOTES SPECIALTY ITEMS, SEE SPECIAL PROVISIONS

PROJECT: CONTRACT: 367, COUNTY: CO. CHAM, ILL.
SECTION: 07-00154-11-TL, SHEET: 04



USER NAME = RBast
DESIGNED - BDC
DRAWN - RCB
CHECKED - APS
DATE - 11/8/11
PLOT SCALE = NONE
PLOT DATE = 11/8/2011

REVISED -
REVISED -
REVISED -
REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION
PROPOSED ROADWAY IMPROVEMENTS
C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30**

SUMMARY OF QUANTITIES
SCALE: NONE SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
367	07-00154-11-TL	WILL	70	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 63597	