

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0021	0042
** 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4		4	
** 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1		1	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3063		3063	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	130		130	
** 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1	
** 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	205		205	
** 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	143		143	
** 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	100		100	
** 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	638		638	
** 81400100	HANDHOLE	EACH	5		5	
** 81400200	HEAVY-DUTY HANDHOLE	EACH	1		1	
** 81400300	DOUBLE HANDHOLE	EACH	2		2	
** 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
** 85700215	RAILROAD, FULLACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1	
** 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1	
** 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	803		803	
** 87300010	GROUND EXISTING HANDHOLE FRAME AND COVER	EACH	3		3	
** 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	777		777	
** 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1592		1592	
** 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3348		3348	
** 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2405		2405	
** 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2432		2432	
** 87301750	ELECTRIC CABLE IN CONDUIT, RAILROAD, NO. 14 3C	FOOT	262		262	
** 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	101		101	
** 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	956		956	
** 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1	
** 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2		2	
** 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1		1	
** 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2		2	
** 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1	
** 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1	
** 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1		1	
** 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16	
** 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
** 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	67		67	
** 87900200	DRILL EXISTING HANDHOLE	EACH	1		1	
** 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	9		9	
** 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2	
** 88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	1		1	
** 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	3		3	
** 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1	
** 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	3		3	

** SEE SPECIAL PROVISIONS
 ** DENOTES SPECIALTY ITEMS, SEE SPECIAL PROVISIONS

PROJECT: ILLINOIS DEPARTMENT OF TRANSPORTATION
 DRAWING: ROADWAY IMPROVEMENTS
 SHEET: 3 OF 6
 DATE: 11/8/2011

SEC Group, Inc.
 An IFC Group Company
 201 Adams Drive
 Naperville, IL 60563
 1-815-462-2000
 www.secgroup.com

USER NAME = RBest
 PLOT SCALE = NONE
 PLOT DATE = 11/8/2011

DESIGNED - BDC
 DRAWN - RCB
 CHECKED - APS
 DATE - 11/8/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROPOSED ROADWAY IMPROVEMENTS
 C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30**

SUMMARY OF QUANTITIES			
SCALE:	NONE	SHEET NO. 3 OF 4 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
367	07-00154-11-TL	WILL	70	6
FED. ROAD DIST. NO.				ILLINOIS FED. AID PROJECT
CONTRACT NO. 63597				