

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0021	0042
** 88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1	
** 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1	
** 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	15		15	
** 88500100	INDUCTIVE LOOP DETECTOR	EACH	12		12	
** 88600100	DETECTOR LOOP, TYPE I	FOOT	1118		1118	
** 88700200	LIGHT DETECTOR	EACH	4		4	
** 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1	
** 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1	
** 89100400	ILLUMINATED SIGN, LED	EACH	2		2	
** 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	8763		8763	
** 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1	
** 89502380	REMOVE EXISTING HANDHOLE	EACH	7		7	
** 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	11		11	
** X0322341	PULL & REINSTALL FIBER OPTIC CABLE	L SUM	1		1	
* X2800510	INLET FILTER CLEANING	EACH	20	20		
* X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1		
* X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	5		
* X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	8504	8504		
* X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	4969	4969		
* X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	1327	1327		
* X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	153	153		
* X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	99	99		
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1	
** X8730320	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 20 3/C, TWISTED, SHIELDED	FOOT	1077		1077	
* Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3429	3429		
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
* Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	125		125	
** Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1		1	
* Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	142	142		
* Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
** Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1	
Z0076600	TRAINEES	HOUR	500			500
** X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1	

* SEE SPECIAL PROVISIONS
** DENOTES SPECIALTY ITEMS, SEE SPECIAL PROVISIONS

PROJECT: 07-00154-11-TL
DRAWING: 07-00154-11-TL-04
DATE: 11/8/2011 11:58:04 AM

SEC Group, Inc.
Illinois Professional Design Firm # 184-02108
An HDR Group Company
223 Avenue Drive
Naperville, Illinois 60563
1-815-462-2200 • FAX 815-462-9120
www.secgroupinc.com
*Henry B. *Hickory, L.L. *New Lanark, IL *Chicago, IL

USER NAME = RBest
PLOT SCALE = NONE
PLOT DATE = 11/8/2011

DESIGNED - BDC
DRAWN - RCB
CHECKED - APS
DATE - 11/8/11

REVISED -
REVISED -
REVISED -
REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION
PROPOSED ROADWAY IMPROVEMENTS
C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30**

SUMMARY OF QUANTITIES			
SCALE:	NONE	SHEET NO. 4 OF 4 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
367	07-00154-11-TL	WILL	70	7
FED. ROAD DIST. NO.				ILLINOIS FED. AID PROJECT
CONTRACT NO. 63597				