

LOCATION	PAVEMENT MARKING TAPE, TYPE III				WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	SHORT-TERM PAVEMENT MARKING (FOOT)
	LETTERS AND SYMBOLS (SQ FT)	4" (FOOT)	6" (FOOT)	8" (FOOT)		
GOUGAR ROAD						
STAGE I						
STA 79+49.00 TO STA 86+21.84	134.6	3,135	138		48	1,344
STA 86+47.71 TO STA 87+16.26		114		176		155
STA 87+97.09 TO STA 97+00.00	97.5	3,597		678	36	1,821
SUBTOTAL STAGE I						
STAGE II						
STA 79+49.00 TO STA 86+21.84	195.0	1,272	236		48	833
STA 86+47.71 TO STA 87+16.26		138	68	132	12	192
STA 87+97.09 TO STA 97+00.00	166.8	2,388	580	240	48	1,509
SUBTOTAL STAGE II						
STAGE III						
STA 79+49.00 TO STA 86+21.84						288
STA 86+47.71 TO STA 87+16.26						80
STA 87+97.09 TO STA 97+00.00						476
STAGE III						
TOTAL	594	10,644	1,022	1,226	192	5,854

*QUANTITY INCLUDES STRIPING OF MAINLINE TO PT OF SIDE ROAD.
 **REMOVAL OF WORK ZONE PAVEMENT MARKINGS FROM STAGE 3 (INCLUDES REMOVAL OF SHORT-TERM MARKINGS PRIOR TO PLACEMENT OF PERMANENT STRIPING).
 ***AT THE CONCLUSION OF STAGE 2, THE PERMANENT PAVEMENT MARKING SHALL BE INSTALLED ON U.S. ROUTE 34 (SEE PAVEMENT MARKING AND SIGNAGE PLAN).

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	POROUS GRANULAR EMBANKMENT SUBGRADE (CU YD)
GOUGAR ROAD						
STA 79+49.00 TO STA 86+21.61	1146	974	621	352	66	66
STA 86+26.00 TO STA 87+16.26	74	63	43	20	4	4
STA 87+58.14 TO STA 97+00.00	1470	1250	273	977	72	72
TOTAL	2690	2286	937	1349	142	142

SHRINKAGE FACTORS
 EARTH EXCAVATION 15%

NOTE:
 CUTS AND FILLS HAVE BEEN ADJUSTED FOR TOPSOIL PLACEMENT.

PROJECT: CHRYSLER, JACOBS & COMPANY, P.C.
 PROJECT NO. 07-00154-11-TL
 SHEET NO. 12

SEC Group, Inc.
 An IRI Group Company
 323 Main Street
 New Lenox, Illinois 60451
 815.462.8241 • 815.462.9328
 www.secgroupinc.com
 MDarryll • Chicago, IL • New Lenox, IL • Chicago, IL

USER NAME = RBest	DESIGNED - BDC	REVISED -
PLOT SCALE = NONE	DRAWN - RCB	REVISED -
PLOT DATE = 11/8/2011	CHECKED - APS	REVISED -
	DATE - 11/8/11	REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROPOSED ROADWAY IMPROVEMENTS
 C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF	SHEETS
NONE	1	OF	4
	TO STA.		

F.A.U. RTE. 367	SECTION NO. 07-00154-11-TL	COUNTY WILL	TOTAL SHEETS 70	SHEET NO. 12
CONTRACT NO. 63597				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				