

LOCATION	CATCH BASINS TYPE A 4" DIAMETER TYPE 24 FRAME AND GRATE (EACH)	INLETS TYPE A TYPE 24 FRAME AND GRATE (EACH)	STORM SEWERS CLASS A TYPE 1 12" (FOOT)	PRECAST REINFORCED CONCRETE FLARED END SECTIONS		GRATING FOR CONCRETE FLARED END SECTION 24" (EACH)	STEEL END SECTIONS		PIPE CULVERTS CLASS D TYPE 1		PIPE CULVERTS CLASS A TYPE 1
				ROUND			ROUND		18" (FOOT)	24" (FOOT)	24" (FOOT)
				12" (EACH)	24" (EACH)		18" (EACH)	24" (EACH)			
GOUGAR ROAD											
80+55.57 RT TO 80+56.00 RT			3								
80+56.00 RT TO 80+56.00 RT	1		30	1							
80+56.00 RT TO 80+62.00 RT		1	3								
81+70.00 RT TO 81+70.00 RT	1		36	1							
82+10.00 RT TO 82+50.00 RT							2		40		
82+85.00 LT TO 82+85.00 RT	1	1	76	1							
84+80.00 LT TO 84+80.00 RT	1	1	76	1							
88+06.71 RT	1										
88+50.70 LT TO 88+95.00 LT		1	37	1							
89+00.56 LT TO 89+00.56 RT					1						116
90+00.00 LT TO 90+00.00 LT		1	23	1							
91+42.00 LT TO 91+42.00 LT		1	16	1							
91+50.00 LT TO 92+66.00 LT											
92+30.00 RT TO 92+73.43 RT		1	44				2		116		
92+70.00 LT TO 92+70.00 LT		1	14	1							
92+73.43 RT TO 92+86.00 RT	1		10	1							
93+18.00 LT TO 93+84.00 LT							2		75		
93+89.00 LT TO 93+89.00 LT		1	13	1							
94+90.00 LT TO 95+70.00 LT							2		80		
96+10.00 RT TO 96+50.00 RT							2		40		
TOTAL	6	9	381	10	1	1	2	8	40	311	116

LOCATION	THERMOPLASTIC PAVEMENT MARKING						PAINT PAVEMENT MARKING - LINE 4" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)
	LETTERS AND SYMBOLS (SQ FT)	LINE 4"	LINE 6"	LINE 8"	LINE 12"	LINE 24"			
GOUGAR ROAD									
STA 79+49.00 TO STA 86+21.84	195.2	3459	1022		110	72	265	45	691
STA 86+47.71 TO STA 87+16.26	15.6	251	680	249	133	82	140	2	397
STA 87+97.09 TO STA 97+00.00	243.2	3617	1214	342	783	76	653	69	1975
TOTAL	454	7327	2916	591	1026	230	1058	116	3063

LOCATION	STANDARD NUMBER (NEW) DESCRIPTION (EXISTING)	SIGN PANEL TYPE 1 (SQ FT)	RELOCATE SIGN PANEL ASSEMBLY TYPE A (EACH)	RELOCATE SIGN PANEL ASSEMBLY TYPE B (EACH)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	BASE FOR TELESCOPING STEEL SIGN SUPPORT (EACH)	SIGN PLACEMENT HEIGHT ABOVE EDGE OF PAVEMENT (FOOT)	CENTERLINE OFFSET
GOUGAR ROAD								
83+85.00 RT	W10-1-3636	7.07			26.0	2	7.0	43
84+50.00 RT	D9-2-2424	4.00			14.0	1	7.5	43
84+50.00 RT	M6-1-2115	2.19			14.0	1	6.5	43
85+00.00 LT	R2-1-2430	5.00			13.0	1	7.0	30
85+55.00 LT	R8-8-2430	5.00			14.5	1	8.5	3
85+55.00 LT	R10-6A-2436	6.00			13.0	1	6.0	3
85+60.00 RT	R8-8-2430	5.00			14.5	1	8.5	43
85+60.00 RT	W10-165-3030	6.25			13.0	1	6.0	43
85+60.00 RT	R10-11-2430	6.00			13.0	1	7.0	45
86+35.00 RT	R8-8-2430	5.00			13.0	1	8.5	49
86+80.00 LT	R8-8-2430	5.00			13.0	1	8.5	2
88+72.00 RT	R3-5R-3036	7.50			26.0	2	7.0	55.5
89+50.00 LT	W10-1-3636	7.07			26.0	2	7.0	38
90+00.00 LT	D9-2-2424	4.00			14.0	1	7.5	38
90+00.00 LT	M6-1-2115	2.19			14.0	1	6.0	38
90+00.00 RT	R2-1-2430	5.00			13.0	1	7.0	55.5
90+77.00 RT	W11-10-3030	6.25			13.0	1	7.0	55.5
91+00.00 LT	M4-5-2412	2.00			15.0	1	9.5	38
91+00.00 LT	M1-1-2424	4.00			15.0	1	7.5	38
91+00.00 LT	M6-1-2115	2.19			15.0	1	6.0	38
91+25.00 RT	W11-2-3030	6.25			13.0	1	7.0	53
91+52.00 LT	R3-5R-3036	7.50			26.0	2	7.0	38
91+95.00 LT	R1-1-3030	6.25			13.0	1	7.0	38
92+05.05 LT	PRIVATE PARKING			1				39
92+10.00 RT	PRIVATE PROPERTY FOR USE OF PROVIDENCE STUDENTS ONLY		1		14.0	1	6.5	39
92+10.00 RT	R3-2-2424	4.00			14.0	1	7.5	39
92+30.00 RT	R4-7A-2430	5.00			13.0	1	7.0	62
92+46.00 RT	R5-1-3030	6.25			13.0	1	7.0	40
92+59.03 LT	DO NOT BLOCK DRIVEWAY 24 HOUR ACCESS REQUIRED		1		13.0	1	6.0	30
92+66.00 RT	R1-1-3030	6.25			30.0	2	8.5	50
92+66.00 RT	R3-5R-3036	7.50			30.0	2	6.0	50
93+22.00 LT	STOP SIGN / THANK YOU BUCKLE UP		1		13.0	1	7.0	33
93+78.51 LT	SHIPPING AND RECEIVING			1				59
93+81.16 LT	DO NOT BLOCK DRIVEWAY 24 HOUR ACCESS REQUIRED		1		13.0	1	6.0	29
95+00.00 LT	STOP SIGN / THANK YOU BUCKLE UP		1		13.0	1	7.0	29
95+50.16 RT	CROSSWALK / FLASHING LIGHT / SOLAR POWER ASSEMBLY		1					29
95+71.24 LT	CROSSWALK / FLASHING LIGHT / SOLAR POWER ASSEMBLY		1					25.5
98+00.00 LT	W11-2-3030	6.25			13.0	1	7.0	23.5
U.S. ROUTE 30								
277+91.00 LT	R3-5R-3036	7.50			26.0	2	7.0	51
TOTAL		160	7	2	569	42		

ALL EXISTING SIGNS TO BE RELOCATED SHALL BE MOUNTED ON NEW METAL POSTS.

**ILLINOIS DEPARTMENT OF TRANSPORTATION
PROPOSED ROADWAY IMPROVEMENTS
C.H. 52 (GOUGAR ROAD) AT U.S. ROUTE 30**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.U RTE.	SECTION NO.	COUNTY	TOTAL SHEETS	SHEET NO.
367	07-00154-11-TL	WILL	70	14
CONTRACT NO. 63597				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

SEC Group, Inc.
 Illinois Professional Design Firm # 154-000108
 An HDR Group Company
 320 Park Drive
 New Lenox, Illinois 80501
 815-462-8204 / 815-462-8208
 www.secgroup.com
 *Mailing: 1100 W. 14th St., New Lenox, IL 80501

USER NAME = RBest	DESIGNED - BDC	REVISED -
PLOT SCALE = NONE	DRAWN - RCB	REVISED -
PLOT DATE = 11/8/2011	CHECKED - APS	REVISED -
	DATE - 11/8/11	REVISED -